	Fernando L. Ribas Dominicci Airport (SIG)											
Site Inspection	D	Secretary of	A A 65	D	Comp	oleted	o	n-Going		Not Sta	rted	
Date	Damage Date	Description	Area Affected	Damage	Yes/No	Date	Yes/No	Completion Date	Responsible Party	Start Date	Project Duration	Project Cost
				Damaged to Wall and Ceiling Wood Paneling; (0% Complete) a. Ceiling, 27 ft. x 12 ft. = 324 SF (Pressed Wood) b. Walls, [(27 ft. x 8 ft.) + 2 (12 ft. x 8 ft.) + 2(10 ft. x 8 ft.)] = 600 SF Damaged Ceiling Lights; (0% Complete)	No		No		FEMA	TBD	TBD	TBD
			East 1st Floor	a. Qty. (3), 2 ft. x 4 ft. Fluorescent Light Fixture Surface Mount (4 bulb type) Damaged Metal Door (Metal Frame) With full Glass insert; (0% Complete) a. Qty. (1) 3 ft. x 7 ft.	No No		No No		FEMA FEMA	TBD TBD	TBD	TBD
				Damaged to Ceramic Floor Tile; (0% Complete) a. Ceramic Tiles Area 27 ft. x 12 ft. = 324 SF	No		No		FEMA	TBD	TBD	TBD
				Damaged to Windows; (0% Complete) a. Jalousie Style Window, Qty. (3) 36 in. x 50 in.	No		No		FEMA	TBD	TBD	TBD
				Damaged to Wall and Ceiling Wood Paneling; (0% Complete) a. Ceiling, 30 ft. x 9 ft. = 270 SF b. Walls, [2(30 ft. x 9 ft.) + 2 (9 ft. x 9 ft.) + 2(9 ft. x 7 ft.)] = 828 SF	No		No		FEMA	TBD	TBD	TBD
				Damaged Ceiling Lights; (0% Complete) a. Qty. (3), 2 ft. x 4 ft. Fluorescent Light Fixture Surface Mount (4 bulb type)	No		No		FEMA	TBD	TBD	TBD
			Offices #3	Damaged Wood Door; (0% Complete) a. Wood Door with Wood Frame, Qty. (2) 3 ft. x 7 ft.	No		No		FEMA	TBD	TBD	TBD
			SW 2nd Floor	Damaged to A/C Unit; (0% Complete) a. Qty. (1), Window Unit (12000 BTU, 120VAC)	No		No		FEMA	TBD	TBD	TBD
				Damaged to Floor Carpet; (high traffic type) (0% Complete) a. Carpet Area 30 ft. x 9 ft. = 270 SF	No		No		FEMA	TBD	TBD	TBD
				Damaged to Glass (Viewing Glass, does not open); (0% Complete) a. Glass with Wood Frame, Qty. (3) 4 ft. x 4 ft. b. Glass with Wood Frame, Qty. (1) 8 ft. x 4 ft.	No		No		FEMA	TBD	TBD	TBD
				Damaged High Traffic Type Carpet Tiles; (0% Complete) 30 ft x 9 ft = 270 Sq. Ft.	No		No		FEMA	TBD	TBD	TBD

Fernando L. Ribas Dominicci Airport (SIG)												
Site Inspection	D		Area Affected		Comp	leted	o	n-Going		Not Star	rted	
Date	Damage Date	Description A	чгеа Апессео	Damage	Yes/No	Date	Yes/No	Completion Date	Responsible Party	Start Date	Project Duration	Project Cost
				Damaged to Acoustic Ceiling Tiles; $(2' \times 4')$ tiles to include installation hardware); (0%) Complete) a. Ceiling, 23 ft. \times 13 ft. = 299 SF	No		No		FEMA	TBD	TBD	TBD
				Damaged Ceiling Lights (T-Bar Drop in Type); (0% Complete) a. Qty. (3), 2 ft. x 4 ft. Fluorescent Light Fixture Drop-In Mount (4 bulb type)	No		No		FEMA	TBD	TBD	TBD
			Offices #4	Damaged Wall Sheet Rock (0% Complete) a. Walls, [2(23 ft. x 8 ft.) + 2(13 ft. x 8 ft.)] = 576 SF	No		No		FEMA	TBD	TBD	TBD
			East 2nd Floor a. V Dan a. C Dan c Cor a. J	Damaged Wood Door; (0% Complete) a. Wood Door with Wood Frame, Qty. (1) 3 ft. x 7 ft.	No		No		FEMA	TBD	TBD	TBD
				Damaged to A/C Unit; (0% Complete) a. Qty. (1), Window Unit (12000 BTU, 120VAC)	No		No		FEMA	TBD	TBD	TBD
				Damaged to Vinyl Tile Flooring; (0% Complete) a. Vinyl Area 23 ft. x 13 ft. = 299 SF	No		No		FEMA	TBD	TBD	TBD
				Damaged to Windows; (Metal Frame with Glass Inserts) (0% Complete) a. Jalousie Style Window, Qty. (3) 54 in. x 24 in. b. Jalousie Style Window, Qty. (1) 54 in. x 28 in.	No		No		FEMA	TBD	TBD	TBD
		b. Jal Dami hardi a. Ce i. Apj Dami Support Support Structure Office #1 SE 1st Floor 1st Floor a. Qt Dami a. Qt Dami a. Qt Dami	Damaged to Acoustic Ceiling Tiles; (2' x 4' tiles to include installation hardware); (0% Complete) a. Ceiling, 12 ft. x 13 ft. = 156 SF i. Approximately 20 Tiles	No		No		FEMA	TBD	TBD	TBD	
			Damaged Ceiling Lights (T-Bar Drop in Type); (0% Complete) a. Qty. (2), 2 ft. x 4 ft. Fluorescent Light Fixture Drop-In Mount (4 bulb type)	No		No		FEMA	TBD	TBD	TBD	
			Damaged Wood Door; (0% Complete) a. Wood Door with Wood Frame, Qty. (1) 3 ft. x 7 ft.	No		No		FEMA	TBD	TBD	TBD	
			Damaged to A/C Unit; (0% Complete) a. Qty. (1), Window Unit (12000 BTU, 120VAC)	No		No		FEMA	TBD	TBD	TBD	
			Damaged to Ceramic Floor Tile; (0% Complete) a. Ceramic Tiles Area 12 ft. x 13 ft. = 156 SF	No		No		FEMA	TBD	TBD	TBD	
			Dama	Damaged to Windows; (0% Complete) a. Jalousie Style Window, Qty. (4) 36 in. x 48 in.	No		No		FEMA	TBD	TBD	TBD

				Fernando L. Ribas Dominicci Airport	t (SIG)							
Site Inspection				_	Comp	leted	o	n-Going		Not Sta	rted	
Date	Damage Date	Description	Area Affected	Damage -	Yes/No	Date	Yes/No	Completion Date	Responsible Party	Start Date	Project Duration	Project Cost
				Damaged to Acoustic Ceiling Tiles; (2' x 4' tiles to include installation hardware) (0% Complete) a. Ceiling, 9 ft. x 13 ft. = 117 SF i. Approximately 16 Tiles	No		No		FEMA	TBD	TBD	TBD
			Support	Damaged Ceiling Lights (T-Bar Drop in Type); (0% Complete) a. Qty. (2), 2 ft. x 4 ft. Fluorescent Light Fixture Drop-In Mount (4 bulb type)	No		No		FEMA	TBD	TBD	TBD
			Office #2 SE	Damaged Wood Door; (0% Complete) a. Wood Door with Wood Frame, Qty. (1) 3 ft. x 7 ft.	No		No		FEMA	TBD	TBD	TBD
				Damaged to A/C Unit; (0% Complete) a. Qty. (1), Window Unit (12000 BTU, 120VAC)	No		No		FEMA	TBD	TBD	TBD
				Damaged to Ceramic Floor Tile; (0% Complete) a. Ceramic Tiles Area 9 ft. x 13 ft. = 117 SF	No		No		FEMA	TBD	TBD	TBD
		0 . 6		Damaged to Windows; (0% Complete) a. Jalousie Style Window, Qty. (4) 36 in. x 24 in.	No		No		FEMA	TBD	TBD	TBD
12/21/2018	9/20/2017	On September the 20th 2017, Hurricane Maria's wind and rain caused subsequent damages and flooding to Isla Grand Airport (SIG) Fernando LuisRibas Dominicci. Fernando Luis Ribas Dominicci Airport is located in San		Damaged to Acoustic Ceiling Tiles; (2' x 4' tiles to include installation hardware) (0% Complete) a. Ceiling, 10 ft. x 13 ft. = 130 SF i. Approximately 17 Tiles	No		No		FEMA	TBD	TBD	TBD
		Juan Puerto Rico, and is owned by the Puerto Rico Ports Authority.	Support	Damaged Ceiling Lights (T-Bar Drop in Type); (0% Complete) a. Qty. (2), 2 ft. x 4 ft. Fluorescent Light Fixture Drop-In Mount (4 bulb type)	No		No		FEMA	TBD	TBD	TBD
				Damaged Wood Door; (0% Complete) a. Wood Door with Wood Frame, Qty. (2) 3 ft. x 7 ft.	No		No		FEMA	TBD	TBD	TBD
				Damaged to A/C Unit; {0% Complete} a. Qty. (1), Window Unit (12000 BTU, 120VAC)	No		No		FEMA	TBD	TBD	TBD
				Damaged to Ceramic Floor Tile; (0% Complete) a. Ceramic Tiles Area 10 ft. x 13 ft. = 130 SF	No		No		FEMA	TBD	TBD	TBD
				Damaged to Windows; (0% Complete) a. Jalousie Style Window, Qty. (4) 36 in. x 24 in.	No		No		FEMA	TBD	TBD	TBD
				Damaged to Acoustic Ceiling Tiles; (2' x 4' tiles to include installation hardware) (0% Complete) a. Ceiling, 28 ft. x 13 ft. = 364 SF i. Approximately 46 Tiles	No		No		FEMA	TBD	TBD	TBD
			Support	Damaged Ceiling Lights (T-Bar Drop in Type); (0% Complete) a. Qty. (5), 2 ft. x 4 ft. Fluorescent Light Fixture Drop-In Mount (4 bulb type)	No		No		FEMA	TBD	TBD	TBD
				Damaged Wood Door; (0% Complete) a. Wood Door with Wood Frame, Qty. (2) 3 ft. x 7 ft.	No		No		FEMA	TBD	TBD	TBD
				Damaged to A/C Unit; (0% Complete) a. Qty. (1), Window Unit (12000 BTU, 120VAC)	No		No		FEMA	TBD	TBD	TBD
				Damaged to Ceramic Floor Tile; (0% Complete) a. Ceramic Tiles Area 28 ft. x 13 ft. = 364 SF	No		No		FEMA	TBD	TBD	TBD
				Damaged to Windows; (0% Complete) a. Jalousie Style Window, Qty. (8) 30 in. x 24 in.	No		No		FEMA	TBD	TBD	TBD

				Fernando L. Ribas Dominicci Airport	t (SIG)		200					
Site Inspection					Comp	leted	0	n-Going		Not Sta	rted	
Date	Damage Date	Description	Area Affected	Damage	Yes/No	Date	Yes/No	Completion Date	Responsible Party	Start Date	Project Duration	Project Cost
				Damaged to Acoustic Ceiling Tiles; (2' x 4' tiles to include installation hardware) (0% Complete) a. Ceiling Front Office, 19 ft. x 13 ft. = 247 SF b. Ceiling Lobby Area, 15 ft. x 13 Ft. = 150 SF i. Approximately 50 Tiles	No		No		FEMA	TBD	TBD	TBD
			Suppport	Damaged Ceiling Lights (T-Bar Drop in Type); (0% Complete) a. Qty. (6), 2 ft. x 4 ft. Fluorescent Light Fixture Drop-In Mount (4 bulb type)	No		No		FEMA	TBD	TBD	TBD
			Structure - Front Entrance and	Damaged Metal Door with Glass Insert; (0% Complete) a. Metal Door with Metal Frame, Qty. (2) 48 In. x 80 in.	No		No		FEMA	TBD	TBD	TBD
			Lobby 1st	Damaged Wood Door; (0% Complete) a. Wood Door with Wood Frame, Qty. (2) 3 ft. x 7 ft.	No		No		FEMA	TBD	TBD	TBD
			Floor	Damaged to A/C Unit; (0% Complete) a. Qty. (1), Window Unit (12,000 BTU, 1 Ton) b. Qty (1) Mini Split Unit (36,000BTU, 3 Ton)	No		No		FEMA	TBD	TBD	TBD
				Damaged to Ceramic Floor Tile; (0% Complete) a. Front Office, 19 ft. x 13 ft. = 247 SF b. Lobby Area, 10 ft. x 15 Ft. = 150 SF	No		No		FEMA	TBD	TBD	TBD
				Damaged to Windows; (0% Complete) a. Jalousie Style Window, Qty. (2) 36 in. x 48 in.	No		No		FEMA	TBD	TBD	TBD
			Di ha a.	Damaged to Acoustic Ceiling Tiles; (2' x 4' tiles to include installation hardware) (0% Complete) a. Ceiling, 25 ft. x 3 ft. = 75 SF i. Approximately 10 Tiles	No		No		FEMA	TBD	TBD	TBD
			907	Damaged to Windows; (0% Complete) a. Jalousie Style Window, Qty. (4) 30 in. x 36 in.	No		No		FEMA	TBD	TBD	TBD
			Structure - Hallway 1st	Damaged to Acrylic Window (Viewing Window, do not open); (0% Complete) a. Acrylic with Wood Frame, Qty. (1) 8 ft. x 4 ft.	No		No		FEMA	TBD	TBD	TBD
				Damaged Ceiling Lights (T-Bar Drop in Type); (0% Complete) a. Qty. (3), 2 ft. x 2 ft. Fluorescent Light Fixture Drop-In Mount (2 bulb type)	No		No		FEMA	TBD	TBD	TBD
				Damaged to Ceramic Floor Tile; (0% Complete) a. Hallway (0% Complete), 25 ft. x 3 ft. = 75 SF	No		No		FEMA	TBD	TBD	TBD
			a. H Dar har a. C i. A Dar Support Structure - IT Room 1st Floor bul Dar a. V Dar	Damaged to Acoustic Ceiling Tiles; (2' x 4' tiles to include installation hardware) (0% Complete) a. Ceiling Office, 8 ft. x 13 ft. = 104 SF i. Approximately 13 Tiles	No		No		FEMA	TBD	TBD	TBD
				Damaged to Windows; (0% Complete) a. Jalousie Style Window, Qty. (4) 30 in. x 36 in.	No		No		FEMA	TBD	TBD	TBD
				Damaged Ceiling Lights (T-Bar Drop in Type); (0% Complete) a. Qty. (2), 2 ft. x 4 ft. Fluorescent Light Fixture Drop-In Mount (4 bulb type)	No		No		FEMA	TBD	TBD	TBD
				Damaged Wood Door; (0% Complete) a. Wood Door with Wood Frame, Qty. (1) 3 ft. x 7 ft.	No		No		FEMA	TBD	TBD	TBD
				Damaged to Ceramic Floor Tile; (0% Complete) a. Ceramic, 8 ft. x 13 ft. = 104 SF	No		No		FEMA	TBD	TBD	TBD

				Fernando L. Ribas Dominicci Airpor	t (SIG)							
Site Inspection	Damaga Bata	Description	Area Affected	Damaga	Comp	leted	o	n-Going		Not Sta	rted	
Date	Damage Date	Description	Агеа Аттестес	Damage	Yes/No	Date	Yes/No	Completion Date	Responsible Party	Start Date	Project Duration	Project Cost
				Damage to Acoustic Ceiling Tiles; (2' x 4' tiles to include installation hardware) (0% Complete) a. Ceiling Office, 21 ft. x 13 ft. = 273 SF i. Approximately 35 Tiles	No		No		FEMA	TBD	TBD	TBD
				Damage to Windows; (0% Complete) a. Jalousie Style Window, Qty. (4) 24 in. x 36 in.	No		No		FEMA	TBD	TBD	TBD
			Loccer Room 1st Floor 1st Floor Damaged Wood Door a. Wood Door with W Damage to Vinyl Floor a. Vinyl Tile, 21 ft. x 1:		No		No		FEMA	TBD	TBD	TBD
				Damaged Wood Door; (0% Complete) a. Wood Door with Wood Frame, Qty. (1) 3 ft. x 7 ft.	No		No		FEMA	TBD	TBD	TBD
				Damage to Vinyl Floor Tile; (0% Complete) a. Vinyl Tile, 21 ft. x 13 ft. = 273 SF	No		No		FEMA	TBD	TBD	TBD
				Damaged to Lockers (0% Complete) a. Qty. (20), Height 16 ft. gray in color	No		No		FEMA	TBD	TBD	TBD
				Damaged to Acoustic Ceiling Tiles; (2' x 4' tiles to include installation hardware) (0% Complete) a. Ceiling Office, 14 ft. x 13 ft. = 182 SF i. Approximately 23 Tiles	No		No		FEMA	TBD	TBD	TBD
				Damaged to Windows; (0% Complete) a. Jalousie Style Window, Qty. (2) 24 in. x 36 in.	No		No		FEMA	TBD	TBD	TBD
			Support Structure -	Damaged Ceiling Lights (T-Bar Drop in Type); (0% Complete) a. Qty. (3), 2 ft. x 4 ft. Fluorescent Light Fixture Drop-In Mount (4 bulb type)	No		No		FEMA	TBD	TBD	TBD
				Damaged Wood Door; (0% Complete) a. Wood Door with Wood Frame, Qty. (1) 3 ft. x 7 ft.	No		No		FEMA	TBD	TBD	TBD
				Damaged to Ceramic Floor Tile; (0% Complete) a. Ceramic Tile, 14 ft. x 13 ft. = 182 SF	No		No		FEMA	TBD	TBD	TBD
			Dar a. C b. C c. C	Damaged Bathroom Fixtures; (0% Complete) a. Qty. (2), 27 in. x 20 in. Sink b. Qty. (1), Urinal c. Qty. (2), Elongated bowl d. Qty. (2), Showers	No		No		FEMA	TBD	TBD	TBD

				Fernando L. Ribas Dominicci Airpor	t (SIG)							
Site Inspection					Comp	leted	C	n-Going		Not Sta	rted	
Date	Damage Date	Description	Area Affected	Damage	Yes/No	Date	Yes/No	Completion Date	Responsible Party	Start Date	Project Duration	Project Cost
				Damaged to Acoustic Ceiling Tiles; $(2' \times 4')$ tiles to include installation hardware) (0% Complete) a. Ceiling Office, 14 ft. \times 13 ft. = 182 SF i. Approximately 23 Tiles	No		No		FEMA	TBD	TBD	TBD
				Damaged to Windows; (0% Complete) a. Jalousie Style Window, Qty. (2) 24 in. x 36 in.	No		No		FEMA	TBD	TBD	TBD
				Damaged Ceiling Lights (T-Bar Drop in Type); (0% Complete) a. Qty. (3), 2 ft. x 4 ft. Fluorescent Light Fixture Drop-In Mount (4 bulb type)	No		No		FEMA	TBD	TBD	TBD
				Damaged Wood Door; (0% Complete) a. Wood Door with Wood Frame, Qty (1) 3 ft. x 7 ft.	No		No		FEMA	TBD	TBD	TBD
				Damaged to Vinyl Floor Tile; (0% Complete) a. Vinyl Tile, 14 ft. x 13 ft. = 182 SF	No		No		FEMA	TBD	TBD	TBD
				Damaged to A/C Unit; (0% Complete) a. Qty. (1), Window Unit (12000 BTU, 120VAC)	No		No		FEMA	TBD	TBD	TBD
			Sleeping Quarters 1st Floor	Notes: 1. Complete building redesign, and substitution recommended. 2. Damaged to Slab it appears to be unstable. 3. Generator needs replacement could not verify operation. 4. Recommend A/E services (Drawings and Scope) for new construction of facility hangar. Work Completed: No permanent work has been completed under Category E at the time of this report. Key Emergency Notes: 1. There is extensive damage to building envelope, with loose wall and roof paneling; building is partially unusable, and represents a security risk. 2. The structure appeared to be poorly maintained with corrosion evident on column, beams, paneling, and anchoring on floor, with some broken structural elements dangling dangerously over the building's habitable space. 3. The building is missing around 30% of its building envelope, over 7,500 sq. ft., and missing some of its structural components. Diesel Generator not operational Pre-Maria. 4. South Side of Hangar has offices that include 2 story wood and steel structure and 1st floor Lobby and main entrance with exterior block walls and interior sheet rock. 5. Complete building redesign, and substitution recommended.	No		No		FEMA	TBD	TBD	TBD

	~			Fernando L. Ribas Dominicci Airpor	t (SIG)		<i>1</i> 0					
Site Inspection	5	Secretary	A A 66	.	Comp	pleted	o	n-Going		Not Sta	rted	
Date	Damage Date	Description	Area Affected	Damage	Yes/No	Date	Yes/No	Completion Date	Responsible Party	Start Date	Project Duration	Project Cost
				Hangar 22 Police Gym (FURA)								
12/21/2018		On September the 20th 2017, Hurricane Maria's wind and rain caused subsequent damages and flooding to Isla Grand Airport (SIG) Fernando LuisRibas Dominicci. Fernando Luis Ribas Dominicci Airport is located in San Juan Puerto Rico, and is owned by the Puerto Rico Ports Authority. Extensive damage throughout building envelope and interior facility (building collapsed). At the time of site inspection building was cleared of debris (by tenant) and only the concrete pad was left.		Damage to metal frame structure: a. 120 ft. long x 60 ft. wide = Approx. footprint 7200 sq. ft. Notes: 1. Building is missing 60% of its envelope. 2. Recommend A/E services (Drawings and Scope) for new construction of facility hangar. 3. HM for contaminated soil (Used Engine Oil) North Wet of Bldg. Area 30 Ft. long x 20 ft. Wide.	No No		No No		FEMA FEMA	TBD	TBD	TBD
				Hangar 23 Police (Small Building)								
		On Forter when the 20th 2017 Houston a Marie de la contract		Damaged to Exterior Door (West Side of Bldg.); (100% Complete Sub recipient to provide documentation) a. 3 ft. Wide x 7 ft. High Aluminum Door. b. Concrete patching (plaster) around door frame.	Yes		Completed		FEMA	TBD	TBD	TBD
		On September the 20th 2017, Hurricane Maria's wind and rain caused subsequent damages and flooding to Isla Grand Airport (SIG) Fernando LuisRibas Dominicci.		Damaged to concrete plaster on underside of eve. (0% Complete) a. 10 ft. x 3 ft. area	No		No		FEMA	TBD	TBD	TBD
12/21/2018	9/20/2017	Fernando Luis Ribas Dominicci Airport is located in San Juan Puerto Rico, and is owned by the Puerto Rico Ports Authority. Minimal damage was noticed on the		Damaged to concrete block for small bldg. West side (area used as picnic area). (0% Complete) a. 4 ft. x 4 ft. concrete block, plaster and paint.	No		No		FEMA	TBD	TBD	TBD
		exterior of the building envelope. There was no access to the interior of the building. However at the time of site inspection building the tenant mentioned there was no damage to the interior of the facility.		Notes: 1. Exterior aluminum door replaced and concrete plaster around door frame completed by tenant. Tenant to provide documentation. 2. No damage to interior of the bldg. (per tenants' comments). 3. Small building next to main bldg. used as a picnic/outside cook area {charcoal}.	No		No		FEMA	TBD	TBD	TBD

	~		199	Fernando L. Ribas Dominicci Airport	t (SIG)							
Site Inspection	Damage Date	Description	Area Affected	Damage	Comp	leted	o	n-Going		Not Sta	rted	
Date	Damage Date	Description	Area Affected	Damage	Yes/No	Date	Yes/No	Completion Date	Responsible Party	Start Date	Project Duration	Project Cost
				Hangar 25 San Juan Jet Charters								
				Exterior Building, 15.625 SF of Insulated Roof Membrane, 125 FT long x 125 FT wide, Driving wind and rain from Hurricane Maria cause the roof membrane damage and now leaks, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
				Exterior Building, 2,500 SF of CMU Wall - 5 FT Tall - 500 LF, Driving wind and rain from Hurricane Maria, roof paneling blown off, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
				Exterior Building, 22,500 SF of Siding / Insulated Panels, Driving wind and rain from Hurricane Maria, Exterior siding / Insulated panels damaged/missing, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
				Exterior Building, Flashing, 600 FT long, Driving wind and rain from Hurricane Maria, flashing blown off and missing, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
				Exterior Building, Gutters, 600 FT long, Driving wind and rain from Hurricane Maria, Gutters blown off and missing, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
				Exterior Building, Downspouts, 250 FT long, Driving wind and rain from Hurricane Maria, Downspouts blown off and missing, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
				Exterior Building, 1,500 SF of Insulated Corrugated Metal roof (lower Structure), 50 FT long x 30 FT wide, Driving wind and rain from Hurricane Maria, Corrugated metal on lower structure damaged/missing., 0% work completed.	No		No		FEMA	TBD	TBD	TBD
				Exterior Building, 1,500 SF of Tile Flooring, Driving wind and rain from Hurricane Maria, Tile Flooring damaged, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
12/21/2018	9/20/2017	On September the 20th 2017, Hurricane Maria's wind and rain caused subsequent damages and flooding to Isla Grand Airport (SIG) Fernando LuisRibas Dominicci.		Exterior Building, 4 each of Spotlights, Driving wind and rain from Hurricane Maria, Spotlights damaged/Missing, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
	-,=0,=01/	Fernando Luis Ribas Dominicci Airport is located in San Juan Puerto Rico, and is owned by the Puerto Rico Ports Authority.		Exterior Building, 2 each of AC Unit 1 (4 Ton) and 1 (2 Ton), Driving wind and rain from Hurricane Maria, Cinder block Wall damaged, 0% work completed.	No		No		FEMA	TBD	TBD	TBD

	7			Fernando L. Ribas Dominicci Airpor	t (SIG)							
Site Inspection	Damaga Data	Description	Area Affected	Damasa	Comp	leted	o	n-Going		Not Sta	rted	
Date	Damage Date	Description	Area Affected	Damage	Yes/No	Date	Yes/No	Completion Date	Responsible Party	Start Date	Project Duration	Project Cost
				Interior Building, 1 each of Structural Column (North East Corner), 12 IN long x 10 IN wide x 40 FT high, Driving wind and rain from Hurricane Maria, Structural Column twisted and bent from other components failure, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
			Interior Building, 1 each of Gable Beam, Driving wind and rain from Hurricane Maria, Gable Beam twisted and bent from other components failure, 0% work completed.	No		No		FEMA	TBD	TBD	TBD	
				Interior Building, 4 each of C- Channel Beams - C-10 - 500 LF, Driving wind and rain from Hurricane Maria, C Channels Missing, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
		Interior	Interior Building, 40 each of Purlins - C-10 - 125 FT, Driving wind and rain from Hurricane Maria, Purlins Missing, 0% work completed.	No		No		FEMA	TBD	TBD	TBD	
				Interior Building, 225 SF of Server IT System Panel, 15 FT long x 15 FT wide, Driving wind and rain from Hurricane Maria, Electrical / Electrical Panels, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
		EI In W 09 In EI Li _I In	Interior Building, 6 each of Lighting (Main Hangar) High Bay - 400 Watt, Driving wind and rain from Hurricane Maria, Lighting missing, 0% work completed.	No		No		FEMA	TBD	TBD	TBD	
			Interior Building, 10 each of Flouresent Lighting (Lower Structure) 2 FT x 4 FT, Driving wind and rain from Hurricane Maria, flourescent Lighting missing, 0% work completed.	No		No		FEMA	TBD	TBD	TBD	
			Interior Building, 25 SF of Telephone System Panal, 5 FT long x 5 FT wide, Driving wind and rain from Hurricane Maria, Electrical / Electrical Panels, 0% work completed.	No		No		FEMA	TBD	TBD	TBD	

				Fernando L. Ribas Dominicci Airpor	t (SIG)							
Site Inspection	SS				Comp	leted	c	n-Going		Not Sta	rted	
Date	Damage Date	Description	Area Affected	Damage	Yes/No	Date	Yes/No	Completion Date	Responsible Party	Start Date	Project Duration	Project Cost
				Hangar 26 Caribbean Aircraft								
				Exterior Building, 6 each of Translucent Panel 6 FT x 10 FT, 6 FT long x 10 FT wide, Driving wind and rain from Hurricane Maria, Skylights damaged/missing, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
				Exterior Building, 4 each of HID Lights, Driving wind and Rain from hurricane Maria, HID lights damaged/missing, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
				Exterior Building, C-Channels/Sub Framing C-10 - 150 LF, 150 FT long, Driving wind and Rain from hurricane Maria, C-channels / Sub Framing Missing, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
			Exterior Building, 1 each of Windows / Louvers, 13 FT wide x 5 FT high, Driving wind and Rain from Hurricane Maria, windows and louvers missing/damaged, 0% work completed.	No		No		FEMA	TBD	TBD	TBD	
		On September the 20th 2017, Hurricane Maria's wind		Exterior Building, Purlins - C-10, 42 FT long, Driving wind and Rain from Hurricane Maria, purlins missing/damaged, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
12/21/2018	9/20/2017	and rain caused subsequent damages and flooding to Isla Grand Airport (SIG) Fernando LuisRibas Dominicci. Fernando Luis Ribas Dominicci Airport is located in San	Exterior	Exterior Building, Gutters, 64 FT long, Driving wind and Rain from Hurricane Maria, Gutters missing / Damaged, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
		Juan Puerto Rico, and is owned by the Puerto Rico Ports Authority.		Exterior Building, 6 each of DownSpouts - 25 FT Long Each, Driving wind and Rain from Hurricane Maria, Downspouts Missing / Damaged, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
				Exterior Building, Flashing, 66 FT long, Driving wind and Rain from Hurricane Maria, flashing damaged/missing, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
				Exterior Building, 1 each of AC Unit - Model Number AWGBC18-C2 - 18,000 BTU, Driving wind and Rain from Hurricane Maria, AC Unit damaged/ Missing, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
				Exterior Building, 1 each of Motorized Hangar Door - 1500 S.F., Driving Wind and rain from hurricane Maria - Hangar Door inoperable, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
				Exterior Building, 5,600 SF of Corrugated Metal Roof Panels, 80 FT long x 70 FT wide, Driving Wind and Rain from hurricane Maria - roof Membrane damaged/Missing, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
				Exterior Building, 1,800 SF of Corrugated Metal Siding Panels, Driving Wind and Rain from hurricane Maria - Corrugated Metal Siding Panels, 0% work completed.	No		No		FEMA	TBD	TBD	TBD

				Fernando L. Ribas Dominicci Airpor	t (SIG)							Î
Site Inspection				_	Comp	leted	0	n-Going		Not Sta	rted	
Date	Damage Date	Description	Area Affected	Damage	Yes/No	Date	Yes/No	Completion Date	Responsible Party	Start Date	Project Duration	Project Cost
				Hangar 27 Million Air							Duration	
				Exterior Building, Corrogated Metal Siding - South Façade, 30 FT long x 30 FT high, Driving wind and rain caused damage to Corrugated Metal Siding, 100% work completed.	Yes		Completed		FEMA	TBD	TBD	TBD
				Exterior Building, 4 each of C- Channels - South Façade C-10, 20 FT long, Driving wind and rain caused damage to C-Channels, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
				Exterior Building, 1 each of Double Door - South Façade - Galvanized Steel, 5 FT wide x 7 FT high, Driving wind and rain caused damage to Exterior walls, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
				Exterior Building, 1,500 SF of Exterior Walls, Driving wind and rain caused damage to Double Door, 100% work completed.	Yes		Completed		FEMA	TBD	TBD	TBD
				Exterior Building, 8,500 SF of Corrugated Steel Roofing, Driving wind and rain caused damage to Steel Roofing, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
			Exterior	Exterior Building, 1 each of Translucent Roof Panel (25 SQ FT), Driving wind and rain caused damage to the Skylight, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
			Exterior	Exterior Building, 4 each of Downspouts - 40 FT , Driving wind and rain caused damage to the Gutters, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
		On September the 20th 2017, Hurricane Maria's wind and rain caused subsequent damages and flooding to		Exterior Building, Flashing 6 Inch, 450 FT long, Driving wind and rain caused damage to the flashing, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
12/21/2018	9/20/2017	Isla Grand Airport (SIG) Fernando LuisRibas Dominicci. Fernando Luis Ribas Dominicci Airport is located in San		Exterior Building, 2 each of Flourescent Lights round bulbs, Driving wind and rain caused damage to external Lights, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
		Fernando Luis Ribas Dominicci Airport is located in San Juan Puerto Rico, and is owned by the Puerto Rico Ports Authority.		Exterior Building, 4 each of LED Flood Lights, Driving wind and rain caused damage to Flood Lights, 100% work completed.	Yes		Completed		FEMA	TBD	TBD	TBD
				Exterior Building, 4,000 SF of Paint , Driving wind and rain caused damage paint, 100% work completed.	Yes		Completed		FEMA	TBD	TBD	TBD
				Exterior Building, 1 each of Rolling door - Entry Gate Motor Damage, Driving wind and rain caused damage to the entry gate motor, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
				Exterior Building, 3 each of AC Units - 55,000 BTU - (3) Each, Driving wind and rain caused damage to AC UNITS, 0% work completed.	No		No		FEMA	TBD	TBD	TBD

				Fernando L. Ribas Dominicci Airpor	t (SIG)							
Site Inspection	Damage Date	Description	Area Affected	Damage	Comp	leted	o	n-Going		Not Sta	rted	
Date	Damage Date	Description	Area Affected	рападе	Yes/No	Date	Yes/No	Completion Date	Responsible Party	Start Date	Project Duration	Project Cost
				Interior Building, 10,000 SF of Gypsum walls (completed), Driving wind and rain caused damage to the Interior Gypsum Walls, 85% work completed.	No		Yes		FEMA	TBD	TBD	TBD
				Interior Building, 2,995 SF of Insulation Panels, 118 FT long x 71 FT wide, Driving wind and rain caused damage to Insulation, 25% work completed.	No		Yes		FEMA	TBD	TBD	TBD
			0.0000000000000000000000000000000000000	Interior Building, 1,500 SF of Ceramic Tiles , Driving wind and rain caused damage to Insulation, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
				Interior Building, 1,500 SF of Accoustical Ceiling tiles 2 FT x 2 FT, Driving wind and rain caused damage to ACT, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
				Interior Building, A/C Ducts - 2' x 1' cross section, 118 FT long x 71 FT wide, Driving wind and rain caused damage A/C Ducts, 100% work completed.	Yes		Completed		FEMA	TBD	TBD	TBD
				Hangar 27 Million Air			<u> </u>					
				Exterior Building, 1,050 SF of Insulated Roof Panels, Driving wind and Rain from hurricane Maria, Roof Panals missing/damaged, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
		On September the 20th 2017, Hurricane Maria's wind		Exterior Building, 1 each of 40 FT Gable Beam, 12 IN wide x 12 IN high, Driving wind and Rain from hurricane Maria, Gable Beam, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
12/21/2018	12/21/2018 9/20/2017 and Isla	and rain caused subsequent damages and flooding to Isla Grand Airport (SIG) Fernando LuisRibas Dominicci. Fernando Luis Ribas Dominicci Airport is located in San	Exterior	Exterior Building, 15 each of 40 LF C-Channel Beams - C-10, Driving wind and Rain from hurricane Maria, C-Channel Beams missing damaged, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
		Juan Puerto Rico, and is owned by the Puerto Rico Ports Authority.		Exterior Building, Insulated Side Panels, 3 FT wide x 8 FT high, Driving wind and Rain from hurricane Maria, Insulated Side Panals missing/damaged, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
				Exterior Building, 35 each of Gable Seal / Soffit Block / Draft Stop, 3 FT long, Driving wind and Rain from hurricane Maria, Gable Seal / Soffit Block / Draft Stop missing, 0% work completed.	No		No		FEMA	TBD	TBD	TBD


	Fernando L. Ribas Dominicci Airport (SIG)												
Site Inspection	1000 m				Comp	leted	C	n-Going		Not Star	rted		
Date	Damage Date	Description	Area Affected	Damage	Yes/No	Date	Yes/No	Completion Date	Responsible Party	Start Date	Project Duration	Project Cost	
				Hangar 31 Hangar Sadamy									
			Exterior	Exterior Building, 350 SF of Corrugated wall Panels, Drving Wind and Rain from Hurricane Maria cause Corrugated Metal Wall Panels to go missing or damaged, 0% work completed.	No		No		FEMA	TBD	TBD	TBD	
		On September the 20th 2017, Hurricane Maria's wind and rain caused subsequent damages and flooding to		Exterior Building, 4 each of Downspouts 20 Foot, Drving Wind and Rain from Hurricane Maria cause downspouts to go missing or damaged, 0% work completed.	No		No		FEMA	TBD	TBD	TBD	
12/21/2018	9/20/2017	Isla Grand Airport (SIG) Fernando LuisRibas Dominicci. Fernando Luis Ribas Dominicci Airport is located in San		Interior Building, 10 SF of Flashing, Drving Wind and Rain from Hurricane Maria cause Flashing to go missing or damaged, 0% work completed.	No		No		FEMA	TBD	TBD	TBD	
	Juan Puerto Rico, and is owned by the Ports Authority.	AND CONTROL OF THE PROPERTY O	Interior	Interior Building, 1,000 SF of Insulation, Drving Wind and Rain from Hurricane Maria cause Insulation to go missing or damaged, 0% work completed.	No		No		FEMA	TBD	TBD TBD TBD TBD		
				Interior Building, 3 each of Accoustical Ceiling tiles, 2 FT long x 4 FT wide, Drving Wind and Rain from Hurricane Maria cause Accoustical Ceiling Tiles to go missing or damaged, 0% work completed.	No		No		FEMA	TBD		TBD	
	Hangar 33 Avia Service												
				Exterior Building, 2 each of Windows and Aluminum Frame 4 FT x 8 FT AND 3 FT x 4 FT, Driving Winds and Rain from hurricane Maria Cause damage to windows, 0% work completed.	No		No		FEMA	TBD	TBD	TBD	
				Exterior Building, 1 each of Motorized Hangar Door - 1500 SQ FT, Driving Winds and Rain from hurricane Maria Cause damage to Motorized Hangar Door, 0% work completed.	No		No		FEMA	TBD	TBD	TBD	
				Exterior Building, 300 SF of Flashings, Driving Winds and Rain from hurricane Maria Cause damage to Flashing, 0% work completed.	No		No		FEMA	TBD	TBD	TBD	
			Exterior	Exterior Building, Gutters 6 Inch, 400 FT long, Driving Winds and Rain from hurricane Maria Cause damage to Gutters, 0% work completed.	No		No		FEMA	TBD	TBD	TBD	
		On September the 20th 2017, Hurricane Maria's wind		Exterior Building, 14,500 SF of Corrugated Metal Roof, Driving Winds and Rain from hurricane Maria Cause damage to Corrugated Metal Roof, 100% work completed.	Yes		Completed		FEMA	TBD	TBD	TBD	
12/21/2018	9/20/2017	and rain caused subsequent damages and flooding to Isla Grand Airport (SIG) Fernando LuisRibas Dominicci. Fernando Luis Ribas Dominicci Airport is located in San		Exterior Building, 2 each of AC Units 1 (2 Ton) and 1 (1.5 Ton), Driving Wind and Rain from Hurricane Maria Caused Damage to AC Units, 0% work completed.	No		No		FEMA	TBD	TBD	TBD	
		Juan Puerto Rico, and is owned by the Puerto Rico Ports Authority.		Exterior Building, 120 SF of Siding Galvalum, Driving Wind and Rain from Hurricane Maria Caused Damage to Siding, 100% work completed.	Yes		Completed		FEMA	TBD	TBD	TBD	

				Fernando L. Ribas Dominicci Airport	t (SIG)							
Site Inspection				_	Comp	leted	О	n-Going		Not Sta	rted	
Date	Damage Date	Description	Area Affected	Damage	Yes/No	Date	Yes/No	Completion Date	Responsible Party	Start Date	Project Duration	Project Cost
				Interior Building, 7,200 SF of Ceiling Insulation Panals 5 FT x 10 FT, Driving Winds and Rain from hurricane Maria Cause damage to Ceiling Insulation Panals, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
				Interior Building, 2 each of Translucent Roof Panels 300 SQ FT, Driving Winds and Rain from hurricane Maria Cause damage to skylights, 100% work completed.	Yes		Completed		FEMA	TBD	TBD	TBD
			Interior	Interior Building, 2 each of Lighting Fixtures - 400 Watt, Driving Winds and Rain from hurricane Maria Cause damage to Light Fixtures, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
				Interior Building, C-Channel Beams C-10, 334 FT long, Driving Wind and Rain caused Damage to C-Channels, 100% work completed. Interior Building, 2 each of Internal Windows 108 Inch x 60 Inch,	nel Beams C-10, 334 FT long, Driving Wind Yes Completed to C-Channels, 100% work completed.		FEMA	TBD	TBD	TBD		
				Driving Wind and Rain from Hurricane Maria caused Damage to Windows, 100% work completed.	No		No		FEMA	TBD	TBD	TBD
				Hangar 34 Isla Grande Flying School								
				Exterior Building, 2,500 SF of Metal Corrugated Roof Panels 50 FT x 50 FT, Driving Wind and Rain from Hurricane Maria caused damage to the Corrugated Roof Panels, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
		On September the 20th 2017, Hurricane Maria's wind	Exterior	Exterior Building, 2 each of Translucent Roof Panels (3 FT x 25 FT), Driving Wind and Rain from Hurricane Maria caused damage to the skylights, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
12/21/2018	9/20/2017	and rain caused subsequent damages and flooding to Isla Grand Airport (SIG) Fernando LuisRibas Dominicci. Fernando Luis Ribas Dominicci Airport is located in San Juan Puerto Rico, and is owned by the Puerto Rico		Exterior Building, 200 SF of Corrugated Metal Siding, Driving Wind and Rain from Hurricane Maria caused damage to the corrugated Metal Siding, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
		Ports Authority.		Interior Building, 500 SF of DryWall Paneling throughout Building, Driving Wind and Rain from Hurricane Maria caused damage to the DryWall Paneling, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
				Interior Building, 17 each of Louver Type windows (3 FT x 5 FT), Driving Wind and Rain from Hurricane Maria caused damage to the Louver Type Windows, 0% work completed.	No		No		FEMA	TBD	TBD	TBD
				Hangar 35 Aviane Service								
				Damaged/Missing North Side Corrugated Metal Roof – 9 FT x 12 FT = 108 S.F.	No		No		FEMA	TBD	TBD	TBD
				Damaged/Missing North Side Roof Underside - Green board - 9 FT x 12 FT = 108 S.F.	No		No		FEMA	TBD	TBD	TBD
		On September the 20th 2017, Hurricane Maria's wind		Damaged/Missing North Side 3 Can Lights - 6 Inch Can Lights (White) = 3 EACH	No		No		FEMA	TBD	TBD	TBD
12/21/2018	9/20/2017	and rain caused subsequent damages and flooding to Isla Grand Airport (SIG) Fernando LuisRibas Dominicci.	Exterior	Damaged/Missing South Side Façade Concrete - 20 FT x 6 FT = 120 S.F.	No		No		FEMA	TBD	TBD	TBD
		Fernando Luis Ribas Dominicci Airport is located in San		Damaged/Missing 12" Round Exhaust Extractor = 3 Each	No		No		FEMA	TBD	TBD	TBD
		Juan Puerto Rico, and is owned by the Puerto Rico Ports Authority.		Damaged/Missing Wind Sock - (1) 18" x 60" = 1 Each	No No		No No		FEMA FEMA	TBD TBD	TBD TBD	TBD TBD
				Damaged/Missing Electrical 4" PVC Conduit = 1 Linear Foot Damaged Fascia – 10 FT x 4 FT x 1 FT	No		No		FEMA	TBD	TBD	TBD
				Damaged Exterior Paint – 15 FT x 15 FT	No		No		FEMA	TBD	TBD	TBD
			Interior	Damaged Interior Gypsum Surfaces - 15 FT x 15 FT + 5 FT x 3 FT	No		No		FEMA	TBD	TBD	TBD

				Fernando L. Ribas Dominicci Airport	(SIG)							
Site Inspection	Damage Date	Description	Area Affected	Damage	Comp	leted	C	n-Going		Not Sta	rted	
Date	Damage Date	Description	Alea Allected	vaniage	Yes/No	Date	Yes/No	Completion Date	Responsible Party	Start Date	Project Duration	Project Cost
				Hangar 37								
		On September the 20th 2017, Hurricane Maria's wind and rain caused subsequent damages and flooding to		Damaged/Missing Hangar Door Hinges Rusted – 50 FT x 20 FT = 1,000 S.F.	No		No		FEMA	TBD	TBD	TBD
12/21/2018	9/20/2017	Isla Grand Airport (SIG) Fernando LuisRibas Dominicci. Fernando Luis Ribas Dominicci Airport is located in San	Evterior	Damaged/Missing South Side – Flood Light Bulbs Burnt out – 120 volt metal Halide = 1 Each	No		No		FEMA	TBD	TBD	TBD
		Juan Puerto Rico, and is owned by the Puerto Rico Ports Authority.		Damaged/Missing East Side Interior – Wall Insulation – 25 FT x 20 FT = 500 S.F.	No		No		FEMA	TBD	TBD	TBD
				Hangar 37								
				12 Inch Round Roof Ventilators = 2 Each	No		No		FEMA	TBD	TBD	TBD
				Security Camera Dome Type outdoor rated = 1 Each	No		No		FEMA	TBD	TBD	TBD
		On September the 20th 2017, Hurricane Maria's wind and rain caused subsequent damages and flooding to	50.000000000000000000000000000000000000	WEST SIDE Barbwire 3[34 FT + 82 FT + 58 FT + 30 FT] = 612 linear Feet	No		No		FEMA	TBD	TBD	TBD
		Isla Grand Airport (SIG) Fernando LuisRibas Dominicci.		Corrugated Metal Roof Rusting – 1 FT x 1 FT	No		No		FEMA	TBD	TBD	TBD
12/21/2018	9/20/2017	Fernando Luis Ribas Dominicci Airport is located in San		2 FT x 4 FT Hangar Lights = 6 Each	No		No		FEMA	TBD	TBD	TBD
				Concrete Slab Area 20 FT x 10 FT = 200 S.F.	No		No		FEMA	TBD	TBD	TBD
		Juan Puerto Rico, and is owned by the Puerto Rico	Interior	125 Amp Service subpanel – 1 Each	No		No		FEMA	TBD	TBD	TBD
		Ports Authority.	interior	Corrugated Metal Roof Rusting – 1 FT x 1 FT	No		No		FEMA	TBD		TBD
				2 FT x 2 FT Acoustical Ceiling Tile shows water intrusion – 1 Each	No		No		FEMA	TBD	TBD	TBD
				Hangar 39 Royal Air Group								
12/21/2018	9/20/2017	On September the 20th 2017, Hurricane Maria's wind and rain caused subsequent damages and flooding to		Rusted Hangar Doors – Rust Proof and Paint – 81 FT x 15 FT = 1,215 S.F.	No		No		FEMA	TBD	TBD	TBD
		Isla Grand Airport (SIG) Fernando LuisRibas Dominicci.	Exterior	Hangar Door Rails – 81 FT	No		No		FEMA	TBD	TBD	TBD
		Fernando Luis Ribas Dominicci Airport is located in San		East Site Siding – 3 FT x 4 FT = 12 S.F.	No		No		FEMA	TBD	TBD	TBD
		Juan Puerto Rico, and is owned by the Puerto Rico		AC Condensing Units – 3 Ton and 5 Ton – 2 Each	No		No		FEMA	TBD	TBD	TBD
				Item 41 Containers Horizon Aviation								
12/21/2018	9/20/2017	On September the 20th 2017, Hurricane Maria's wind and rain caused subsequent damages and flooding to Isla Grand Airport (SIG) Fernando LuisRibas Dominicci. Fernando Luis Ribas Dominicci Airport is located in San Juan Puerto Rico, and is owned by the Puerto Rico	Exterior		Yes		Completed		FEMA	TBD	TBD	TBD
		Ports Authority.		Damaged/Missing Trailer 15 FT x 30 FT = 1 EACH 100% Completed								

	Fernando L. Ribas Dominicci Airport (SIG)											
Site Inspection	Damasa Bata	Description	Area Affected	Damage	Completed		On-Going		Not Started			
Date	Damage Date	Description	Area Arrected	рападе	Yes/No	Date	Yes/No	Completion Date	Responsible Party	Start Date	Project Duration	Project Cost
				Item B42 Trailer Office Horizon							,	
		On September the 20th 2017, Hurricane Maria's wind		Siding – (8 FT x 4 FT) + 4 FT x 4 FT) +(2 FT x $\frac{1}{2}$ FT) = 49 S.F.	No		No		FEMA	TBD	TBD	TBD
12/21/2018	9/20/2017	and rain caused subsequent damages and flooding to	Exterior	DownSpouts 8 FT long – 4 Each	No		No		FEMA	TBD	TBD	TBD
		Isla Grand Airport (SIG) Fernando LuisRibas Dominicci.		Gutters – 20 LF	No		No		FEMA	TBD	TBD	TBD
	Item B43 Trailer Office Horizon											
12/21/2018	9/20/2017	On September the 20th 2017, Hurricane Maria's wind and rain caused subsequent damages and flooding to Isla Grand Airport (SIG) Fernando LuisRibas Dominicci. Fernando Luis Ribas Dominicci Airport is located in San Juan Puerto Rico, and is owned by the Puerto Rico Ports Authority.	Exterior	Damaged/Missing – Lattice – 45 Linear FT	No		No		FEMA	TBD	TBD	TBD
				General Site								
12/21/2018	9/20/2017	On September the 20th 2017, Hurricane Maria's wind and rain caused subsequent damages and flooding to Isla Grand Airport (SIG) Fernando LuisRibas Dominicci. Fernando Luis Ribas Dominicci Airport is located in San Juan Puerto Rico, and is owned by the Puerto Rico Ports Authority.	Exterior	No Damages claimed by PRPA. (Taxiways, Runways, lights, signs, fences) Pre Storm Damage for the Breakwater/Seawall - applicant must submit for this under 404	No		No		FEMA	TBD	TBD	TBD


APPENDIX C PMMP PAVEMENT



Source: PRPA and Kimley Horn and Associates, Inc, 2016

<u>APPENDIX D</u>

FAA FORM 5010-1 MASTER RECORD



	ENT OF TRANSPO		AIRPORT MAS	TER RECO	RD	PRINT DATE: AFD EFF FORM APPRO	03/31/2021 03/25/2021 OVED OMB 2120-0	015
> 1 ASSOC CITY: > 2 AIRPORT NAME: 3 CBD TO AIRPORT (N		AN NDO LUIS RIBAS	4 STATE: PR DOMINICCI 6 REGION/ADO	D: ASO /ATL	7 SECT	SIG TY:PUERTO RICO, PR AERO CHT: PUERTO RGIN ISLANDS	FAA SITE NR:	53180.*A
10 OWNERSHIP: > 11 OWNER: > 12 ADDRESS: > 13 PHONE NR: > 14 MANAGER: > 15 ADDRESS:	PUBLIC PUERTO RICO P GPO BOX 362829 SAN JUAN, PR 0 (787) 729-8715 GPO BOX 362829 SAN JUAN, PR 0) 0936-2829	Υ	> 70 FUEL: > 71 AIRFRAME > 72 PWR PLAN > 73 BOTTLE O > 74 BULK OXY 75 TSNT STO 76 OTHER SE	E RPRS: IT RPRS: XYGEN: GEN: RAGE: RVICES:	NONE NONE TIE AFRT,AVNCS,CHTR,	BASED AI 90 SINGLE ENG: 91 MULTI ENG: 92 JET: 93 HELICOPTER TOTAL: 94 GLIDERS: 95 MILITARY:	93 50 16
> 16 PHONE NR: > 17 ATTENDANCE SCH MONTHS ALL	787-729-8715 HEDULE: DAYS ALL		HOURS 0600-1930			INSTR,RNTL	96 ULTRA-LIGHT	
18 AIRPORT USE: 19 ARPT LAT: 20 ARPT LONG: 21 ARPT ELEV: 22 ACREAGE: > 23 RIGHT TRAFFIC. > 24 NON-COMM LANDI 25 NPIAS/FED AGREE > 26 FAR 139 INDEX:	66-5-54.9 9.8 SUR' 102 27 NG: YES			> 80 ARPT BCN: > 81 ARPT LGT: BCN LGT: BCN LGT: S 82 UNICOM: > 83 WIND INDIC 84 SEGMENTS 85 CONTROL: 86 FSS: 87 FSS ON AR 88 FSS PHONI 89 TOLL FREE	SKED: KED: CATOR: ED CIRCLE TWR: PT: E NR:	LITIES CG SEE RMK SS-SR YES-L E: NONE YES SAN JUAN NO 1-800-WX-BRIEF	OPERA* 100 AIR CARRIE 102 AIR TAXI: 103 G A LOCAL: 103 G A LOCAL: 105 MILITARY: 105 MILITARY: TOTAL: OPERATIONS FO	R: 0 12,837 37,076 43,375 2,509 95,797
RUNWAY D. RUNWAY DENT: RUNWAY IDENT: 31 LENGTH: 32 WIDTH: 32 WIDTH: 33 SURF TYPE-COND 34 SURF TYPE-COND 35 GROSS WT: 36 (IN THSDS) 37 38 39 PCN: LIGHTING/APC 40 EDGE INTENSITY: 42 RWY MARK TYPE-COND 44 CONTROL AND CONTROL 45 VISUAL GLIDE AND 46 CNTRLN-TDZ: 47 RVR-RVV: 48 REIL: 49 APCH LIGHTS: OBSTRUCTION 50 FAR 77 CATEGORY 51 DISPLACED THR: 52 CTLG OBSTN: 53 OBSTN MARKED/L 54 HGT ABOVE RWY IDENT: 55 DIST FROM RWY IDENT: 56 CNTRLN OFFSET: 57 OBSTN CLNC SLOID 58 CLOSE-IN OBSTN: 58 CLOSE-IN OBSTN: 59 CLOSE-IN OBSTN: 50 TAKE OFF RUN AV 61 TAKE OFF RUN AV 61 TAKE OFF RUN AV 61 TAKE OFF RUN AV 63 LANDER STRUCTURE AV 61 TAKE OFF RUN AV 61 TAKE OFF RUN AV 63 LANDER STRUCTURE AV 63 LANDER STRUCTURE AV 66 TAKE OFF RUN AV 67 TAKE OFF RUN AV 67 TAKE OFF RUN AV 68 SILNDER STRUCTURE AV 68 SILNDER STRUCTURE AV 69 TAKE OFF RUN AV 61 TAKE OFF RUN AV 61 TAKE OFF RUN AV 61 TAKE OFF SILNT AV 61 TAKE OFF S	: : : : : : : : : : : : : : : : : : :		IANGES OCCUR TO ITEM					
> 110 REMARKS: 110-027 RWY 09: TI 110-029 SAN JUAN 110-030 CAUTION I 110-031 3 LGTD CR 110-032 WHEN TWI	HLD 300' BAY CRUISE SHIF DEPARTING RWY RANES 346 FT HIG R CLSD CTC SAN	P MANEUVERING 9; OBSTRUCTION H 0.5 MI SE AER JUAN CERAP AT		ALL VESSEL OBSTE MARINA. B RIGHT TFC PAT F	RUCTION (ON FINAL APPROACH TO	RWY 9 OR DEPAR	TING RWY 27.

APPENDIX E AIRPORT PICTURES

Overview:







Runway:















Taxiway:













Terminal Apron:

















Tenant Hangars / Aprons:












































































Curbfront / Parking:























Perimeter:



















ATCT:



ARFF:



FUEL:



<u>APPENDIX F</u>

EQUIPMENT TRANSFER LIST

Equipment and Tool Inventory Transfer for SIG

Date:

						Date :			
				Serial	Item Book	3	Under	Remaining	
	Item Description	Make	Model			Condition		_	Comments
				Number	Value		Warranty	Life (Years)	
1	SILLA AREA DE ESPERA			27107					
	SILLA AREA DE ESPERA			27108					
	SILLA AREA DE ESPERA			27109					
	SILLA AREA DE ESPERA			271109					
	SILLA AREA DE ESPERA			27111					
	SILLA AREA DE ESPERA			27112					
	SILLA AREA DE ESPERA			27113					
8	SILLA AREA DE ESPERA			27114					
9	SILLA AREA DE ESPERA			27115					
	SILLA AREA DE ESPERA			27116					
	SILLA AREA DE ESPERA			27117					
	SILLA AREA DE ESPERA			27118					
	SILLA AREA DE ESPERA			27119					
	SILLA AREA DE ESPERA			27120					
	SILLA AREA DE ESPERA			27121					
	Silla area de Espera			27122					
17	SILLA AREA DE ESPERA			27123					
18	SILLA AREA DE ESPERA			27124					
	COMPUTADORA	DELL	OPTIPLEX 380	38313					
	COMPUTADORA	DELL	OPTIPLEX 745	35638					
21	COMPUTADORA	DELL	OPTIPLEX 380	38161					
22	COMPUTADORA	DELL	OPTIPLEX 745	35656					
	ARMARIO	GLOBAL	10.444	27732					
	RADIO	ICOM	IC-414	39037					
	RADIO	ICOM	IC-415	39038					
	RADIO	ICOM	IC/A200	37005					
27	RADIO	HARRIS	TP9400	40216					
	RADIO	HARRIS	TP9401	40217					
	RADIO	HARRIS	TP9402	40218					
	RADIO	HARRIS	TP9403	40219					
31	VEHICULO	FORD	ESCAPE	99838					
31	VENICOLO	IOND	LOCAPE	<i>55</i> 050					
32	DARREDOE:	EDELC:	A 7 7551	00005					
	BARREDORA	FREIGHTLINER	A7 ZEPHYR	99866					
	ESCALERA ALUMINIO			32337					
34	ESCALERA ALUMINIO 6'	KELLER		32339					
35	ESCALERA ALUMINIO 10'			13769					
	SILLAS DE OFICINA			25425					
	SILLAS DE OFICINA			25419					
	SILLAS DE OFICINA			25426					
	SILLAS DE OFICINA					×			
				39040					
.0	NEVERA			21385					
41	SUMADORA	ADLER ROYAL	1228-PD	21708					
42	BOMBA DE ASPERJAR	OLDHAM		38128					NO SIRVE
	BOMBA DE ASPERJAR			40394					
	ZERO TURN	KUBOTA	ACS 60	40397					
	CAJA FUERTE	MEILINK	AC3 00	7808					
		IVICILIINK							
	SILLAS DEL COMEDOR			21203					
	SILLAS DEL COMEDOR			23508					
	SILLAS DEL COMEDOR			23509					
49	SILLAS DEL COMEDOR			21205					
50	TRACTOR	MC CORMICK		39569					
51	SILLA			20101					
	ARMARIO DE METAL			10315					
	ARMARIO DE METAL			10316					
	ARMARIO DE METAL			10317					
	MAQUINA LAVAR PISO 20"			23692					
	TANQUE DE AIRE	15014	MOD 401	10520					
	RADIO MOBIL	ICOM	4=05::	25340					
	MAQUINA PARA BRILLAR	IDS	1500U	36263					
	TRIMMER	RED MAX	BC3401 DL	37006					
60	MAQUINA DE BRILLAR	TORNADO	P1600	37414					
61	TOW BAR			30315					
62	VACCUM CLEANER			30324					
	SIERRA CORTAR ARBOLES	MAKITA		30604					
	BLOWER	STIHL	BR350	39548					
	TRIMMER	STIHL		39546					
	TRIMMER	STIHL		39547					
	SILLAS PLEGADIZAS BLANCA	>1E		94406					
	SILLAS PLEGADIZAS BLANCA			94421					
	SILLAS PLEGADIZAS BLANCA			94396					
	SILLAS PLEGADIZAS BLANCA			94350					
	SILLAS PLEGADIZAS BLANCA			94467					
	SILLAS PLEGADIZAS BLANCA			94429					
73	SILLAS PLEGADIZAS BLANCA			94567					
	SILLAS PLEGADIZAS BLANCA			94544					
	SILLAS PLEGADIZAS BLANCA			94450					
	SILLAS PLEGADIZAS BLANCA			94530					
	SILLAS PLEGADIZAS BLANCA			94571					
		 		94571					
_	SILLAS PLEGADIZAS BLANCA								
	SILLAS PLEGADIZAS BLANCA	ļ		94469					
	SILLAS PLEGADIZAS BLANCA			94461					
	SILLAS PLEGADIZAS BLANCA			94510					
82	SILLAS PLEGADIZAS BLANCA			94404					
83	SILLAS PLEGADIZAS BLANCA			94386					
	SILLAS PLEGADIZAS BLANCA			94381					
	SILLAS PLEGADIZAS BLANCA			94398					
	SILLAS PLEGADIZAS BLANCA			94641					
	SILLAS PLEGADIZAS BLANCA			94468					
	SILLAS PLEGADIZAS BLANCA			94349					
	SILLAS PLEGADIZAS BLANCA			94441					
90	SILLAS PLEGADIZAS BLANCA			94562					

Equipment and Tool Inventory Transfer for SIGDate:

			Date :	Date:						
Item Descr	iption	Make	Model	Serial Number	Item Book Value	Condition	Under Warranty	Remaining Life (Years)	Comments	
91 SILLAS PLEGADIZA	AS BLANCA			30168						
92 SILLAS PLEGADIZA				26466						
93 SILLAS PLEGADIZA	AS BLANCA			26616						
94 SILLAS PLEGADIZA				35790						
95 SILLAS PLEGADIZA				16364						
96 DESFIBRILADOR				37531						
97 4 MODULOS DE C	FICINA									
98 R-19		2001	E_ONE	#P 25361						
99 Nitrogen tank		2001	L_OIVE	#1 E3301						
100 2-Fire Hous 1.5										
101 1-Fire Hose 2.5										
102 2 -Spanner Wrenc	h									
103 1-Adjustable Hydr										
104 1-Fire hous Wey V	Jalvo 2.5									
105 Nozzel 1.5 w contr	rol									
106 1 Pick Fire Axe	101									
107 1- BC Fire Extingui	ichar									
108 1- Rescue Kit	isitei									
	1									
109 2- Truck Metal Ch		2011	FFOVI	#D00C44						
110 R-5		2011	550XL	#P99644						
111 1-Medical Equipm	nent Kit									
112 1- Long Board										
113 1- CPR Board										
114 1- K-12										
115 1-Fire Press Hose										
116 1- 15 Pounds Ham										
117 1- Rescue Tool Kit	:									
118 1- 36"Scissor										
119 1-Pump Holmatro										
120 1-32 f. Holmatro H	lose									
121 1- Spreader										
122 1-Cutter										
123 4- PKP Fire Exting	uisher									
124 1- CO2 Fire Exting	uisher									
125 1-Metal X										
126 3- Pick Fire Axe										
127 1- Adjustable Hyd	rant Wrench									
128 1-14"Dimond Disc	For Cutting									
129 4- Large Shovel										
130 2- Nozzles 2.5										
131 2- Fire Hse 2.5										
132 3-Nozzles 1.5										
133 5- Fire Nozzles 1.5										
134 2- Fire Adapter 2.5										
135 1 Fire Hose Wye										
136 1-Floor Brush										
137 2- Machete										
138 1- Camilla de Pala										
139 Escritorio			#P 26641							
140 Silla Reclinable			#P 38181							
141 Silla Reclinable			#P 39179							
142 Archivo			#P18705							
143 Nevera			#P 32988							
144 Estufa			#P 39702							
145 Calculadora			#P 39702 #P 26686							
146 AED			#P36914							
140 MED			"F30514							

APPENDIX G

GENERAL AIRPORT CONTRACTED SERVICES

	Contract Services at the Airport												
Client	Start Date	End Date	Concept	Service Type									
Miguel Quiñones d/b/a PMM Business Intelligence	23-Jan- 2019	30-Jun-2019	Professional Services for Air Route development	Professional									
ST. James Security Services, Inc.	29-Mar- 2019	30-Jun-2019	Surveillance services by security guards in different facilities of the Authority.	Professional									

Source: PRPA, 2019

<u>APPENDIX H</u>

LIST OF ACRONYMS

List of Acronyms

AAC Asphalt Concrete Overlay on Asphalt Concrete

AC Asphalt Concrete

ACIP Airport Capital Improvement Program

AIT Advanced Imaging Technology

APBN Airport Rotating Beacon

ARFF Aircraft Rescue and Fire-Fighting

ALP Airport Layout Plan

APC Asphalt Concrete Overlay on Portland Cement Concrete

ASDA Accelerated Stop Distance Available

AST Atlantic Standard Time
ATCT Airport Traffic Control Tower

AWOS Automated Weather Observation System

BIL Bipartisan Infrastructure Law
CFR Code of Federal Regulations
CIP Capital Improvement Program
COVID-19 Coronavirus Disease 2019

FAA Federal Aviation Administration
FAR Federal Aviation Regulation
FBO Fixed Based Operator

FCT Federal Contract Tower

FEMA Federal Emergency Management Agency

FY Fiscal Year

GA General Aviation

LDA Landing Distance Available

MITL Medium Intensity Taxiway Lights

MRO Maintenance, Repair, and Overhaul hangar

NAVAIDS Navigational Aid Systems

NPIAS National Plan of Integrated Airport Systems

PAPIs Precision Approach Path Indicators
PCC Portland Cement Concrete Pavement

PCI Pavement Condition Index

PMMP Pavement Maintenance and Management Plan

PMP Pavement Management Program
PPPA Public-Private Partnership Act

PR Puerto Rico

PRASA Puerto Rico Aqueduct and Sewer Authority
PRIDCO Puerto Rico Industrial Development Company

PRPA Puerto Rico Ports Authority
REIL Runway End Identifier Lights

RAPMMP Regional Airport Pavement Maintenance and Management Plan

RVR Runway Visual Range

SF Square Feet

SIG Fernando Luis Ribas Dominicci Airport

STIP Statewide Transportation Improvement Program

TAF Traffic Area Forecast

TODA Takeoff Distance Available
TORA Takeoff Run Available

TSA Transportation Security Administration

U.S. United States

VOR Very High-Frequency Omni-Directional Radio Range

Technical Report

Antonio Rivera Rodríguez Airport (VQS)





Technical ReportAntonio Rivera Rodríguez Airport

Version No. 3.0 May 2023

RS&H No.: 242-0047-000

Prepared by RS&H, Inc. at the direction of Puerto Rico Public Private Partnerships Authority



TABLE OF CONTENTS

1	Intro	duction	1
	1.2	Report Disclaimers Document Contents Current Condition	1
2	Airpo	rt Setting and Classification	5
	2.1	Location and Regional Setting	5
	2.2	Federal Role and Classification	5
		State Role and Classification	
	2.4	Operations and Management Structure	7
3	Airfie	ld Facilities	10
	3.1	Runway System	10
	3.1.1	Declared Distances	12
	3.1.2	Pavement Condition	12
	3.2	Taxiway System	12
	3.3	Aprons	14
	3.4	Navigational Aids	15
4	Passe	nger Terminal Facilities	16
	4.1	General Information	16
		Aircraft Parking Positions and Gates	
	4.3	Terminal Building Overview	16
5	Lands	side Facilities	21
		Regional Roadway Connectivity	
		Airport Access Roadway System	
		Terminal Curbfront	
		Commercial Vehicle and Rental Car Facilities	
6		nt Facilities	
O			
		Cargo Facilities	
		Other Tenant Facilities	
7		rt Support Facilities	
•	-	Airport Traffic Control Tower	
		Aircraft Rescue and Fire-Fighting Facilities	
		Airport Maintenance Facilities	
		Aircraft Fueling Facilities	

7.5		Additional Airport Developable Areas	23
8 <i>A</i>	∖viati	on Activity Summary	24
8.1		Historic Aviation Activity	24
8	3.1.1	Passenger Activity	24
3	3.1.2	Air Service	
8	3.1.3	Aircraft Operations	24
8	3.1.4	Based Aircraft	25
3	3.1.5	Cargo Activity	25
8.2		Future Aviation Activity Projections	26
8	3.2.1	Passenger Activity	27
8	3.2.2	Aircraft Operations	
3	3.2.3	Based Aircraft	29
8	3.2.4	Cargo Activity	30
9 (Capita	al Improvement Program	31
9.1		Current ACIP Summary	31
9.2		Bipartisan Infrastructure Bill	
Арреі	ndix A	Airport Layout Plan	33
Арреі	ndix E	FEMA Repairs	35
Арреі	ndix (PMMP Pavement	39
Арреі	ndix E	FAA Form 5010-1 Master Record	41
Арреі	ndix E	Airport Pictures	44
Арреі	ndix F	Equipment Transfer List	62
Арреі	ndix (General Airport Contracted Services	64
Арреі	ndix H	H List of Acronyms	66

LIST OF TABLES

Table 3-1 Runway Charcteristics	10
Table 3-2 Declared Distances	12
Table 3-3 Taxiway Characteristics	14
Table 3-4 Apron Characteristics	14
Table 3-5 NAVAIDs	15
Table 6-1 Tenant Activity	22
Table 8-1 Historic - VQS Airport Statistics	25
Table 8-2 Aviation Forecasts - VQS (2022-2042)	26
Table 9-1 Airport Capital Improvement Program and Funding Sources (\$000)	31
LIST OF FIGURES	
Figure 2-1 Airport Location and Vicinity Map	
Figure 3-1 VQS Airfield Layout	
Figure 4-1 VQS Landside and Tenant Facilities	
Figure 4-2 Terminal Layout Plan Level 1	18
Figure 4-3 Terminal Layout Plan Level 2	19
Figure 4-4 Terminal Administrative Space	20
Figure 8-1 Enplaned Passenger Forecast (2022-2042)	27
Figure 8-2 Operations Forecast (2022-2042)	
	28
Figure 8-3 Based Aircraft Forecast (2022-2042)	

1 INTRODUCTION

The Government of Puerto Rico through the Puerto Rico Public Private Partnerships Authority (PPPA) is exploring the possible transfer of the operation, maintenance, development, and administration of nine regional airports to the private sector through a Public Private Partnership (P3). This includes the Antonio Rivera Rodriguez Airport (VQS or the Airport) in Vieques. The Public-Private Partnership Authority Act (Act 29) requires the PPPA to conduct a study on desirability and convenience to determine whether establishing such partnership is advisable.

1.1 REPORT DISCLAIMERS

The main objective of this technical report is to provide readers with a high-level technical overview of Antonio Rivera Rodriguez Airport in support of the Desirability and Convenience Study required by Act 29. The report and its content are only provided for informational purposes and its content should not be construed as a conditions report or any other form of technical report. Even though the information included in the report was obtained from the Puerto Rico Ports Authority and other reliable sources, RS&H, Inc. does not make any warranties about their completeness, reliability, or accuracy. Use of the information included in this report is at the risk of the user/reader.

1.2 DOCUMENT CONTENTS

The main purpose of this document is to provide readers with a high-level overview of existing facilities and operational areas of the Airport.

The report is organized under the following topics:

- » Airport Setting and Classification;
- » Airfield Facilities;
- » Passenger Terminal Facilities;
- » Landside Facilities;
- » Tenant Facilities;
- » Airport Support Facilities;
- » Aviation Activity Summary;
 - Historic Aviation Activity;
 - Future Aviation Activity Projections; and
- » Capital Improvement Program.

1.3 CURRENT CONDITION

The following pictures provide a visual representation of current conditions of each of the major components at the Airport as of the middle of January 2019. Additional pictures are provided in **Appendix E** of this report.

Appendix B of this report provides a list of repairs identified by PRPA to the Federal Emergency Management Agency (FEMA) as damages caused by Hurricane Maria in September 2017. These repairs are to be funded by FEMA. The preliminary cost estimates for VQS are approximately \$1,500,000. These FEMA repairs are projected to commence in Q3 2019.¹

General Overview



Source: RS&H, Inc., 2019

Runway





Source: RS&H, Inc., 2019

Antonio Rivera Rodriguez Airport (VQS)

¹ The preliminary cost, project progress, and date of commencement are estimated values and the actual value and commencement of the repairs might change once the procurement process is implemented. Some of the repair projects are being implemented by PRPA and are included in the capital improvement plan included in section 9.1.

Taxiway





Source: RS&H, Inc., 2019

Terminal Apron





Source: RS&H, Inc., 2019

Terminal Building





Source: RS&H, Inc., 2019

Access Road, Curbfront and Parking





Source: RS&H, Inc., 2019

2 AIRPORT SETTING AND CLASSIFICATION

2.1 LOCATION AND REGIONAL SETTING

The Municipality of Vieques is located on an Island to the east of Puerto Rico, approximately 65 miles southeast of San Juan. Based on the 2020 U.S. Census, the population of the Municipality of Vieques was 8,249².

The Airport is located approximately 4.5 miles northwest of the Vieques city center, just north and west of Puerto Rico Route 200. **Figure 2-1** shows the Airport's general location and vicinity.

2.2 FEDERAL ROLE AND CLASSIFICATION

The Federal Aviation Administration (FAA) through the National Plan of Integrated Airport Systems (NPIAS) has designated VQS as a primary, non-hub commercial service airport. Primary commercial service airports are publicly owned airports with scheduled air carrier service and at least 2,500 annual enplanements. As a primary airport, VQS is also further designated as a non-hub airport in the NPIAS. Non-hub airports receive less than 0.5 percent of the annual U.S. commercial enplanements but more than 10,000 of the annual U.S. commercial enplanements².

2.3 STATE ROLE AND CLASSIFICATION

The PRPA Aviation System Plan defines four functional levels in their classification system for Puerto Rico's airports:

- » International Commercial;
- » Large Commercial;
- » Regional Commercial; and
- » General Aviation.

VQS is currently classified as a Regional Commercial Airport in the PRPA Aviation System Plan. Under the system plan classification:

"Regional Commercial airports often play a unique role in the Commonwealth's economy. These airports have differentiated themselves by providing vital connections to regions of the Commonwealth that cannot be accessed efficiently. These airports support a variety of air taxi and charter companies, as well as many other general aviation activities.."

² https://factfinder.census.gov/faces/nav/jsf/pages/community_facts.xhtml

³ Puerto Rico Interactive Planning System Technical Report, Puerto Rico Aviation Demand Classification Definitions, Wilbur Smith Associates, 2007.

FIGURE 2-1
AIRPORT LOCATION AND VICINITY MAP



Source: RS&H, Inc., 2021.

2.4 OPERATIONS AND MANAGEMENT STRUCTURE

PRPA currently uses the following structure to manage the nine Airports. At the top of the administrative structure is the Director of the Aviation Bureau, who oversees the administration for all nine Airports. Each Airport has a designated manager supervised by the Director of the Aviation Bureau. **Figure 2-2** provides a general organization chart for the aviation bureau. The Airport Manager for each Airport is responsible for directing, coordinating, and reviewing all aircraft operations, maintenance of the airfield, facilitating community relations, overseeing finances, and reporting Airport statuses to the Director. The Airport Manager is responsible for the following:

- » Airport personnel and scheduling;
- » Airport Operations;
 - VQS is fully staffed from 0600 1830⁴
- » Airport Maintenance
- Support and Coordinate with the Authority's Engineering and Construction Bureau implementation of repairs and Capital Projects;
- Development of the Airport to include evaluating needs, studying areas of improvement, and implementing plans for improvement;
- » Anticipated Capital Improvement Projects; and
- » Daily Airport Safety and Security Inspections.

Major Airport improvement and repairs at all Airports are executed through a centralized Capital Improvement Program (CIP) managed by the Authority's division of planning and engineering. The CIP helps identify a list of projects, their priority, and implementation timeline for the Airport over a five-year period. The CIP is reviewed and approved on an annual basis by the Authority's Board and eligible projects are coordinated with the FAA. The projects are then funded from various funding sources including FAA grants and Authority's own funding.

The number one responsibility of the Authority and each Airport manager is to provide for the safety and efficiency of the Airport. The Airport Manager is not only responsible for reporting to the Director, but the Airport Manager is also responsible for conveying the Airport functions and activities to the community. The management functions included in the role of Airport Manager are:

- » Planning;
- » Organizing;
- » Staffing;
- » Leading; and
- » Controlling.

PRPA manages the nine publicly owned airports and are subject to a number of Federal, State, and Local regulations. These regulations help to regulate aircraft, airmen, airports, and airspace. The Federal


-

⁴ https://www.airnav.com/airport/TJVQ

Regulations are identified in *Title 14 U.S. Code of Federal Regulations (CFR), Chapters I and II, Federal Aviation Regulations (FARs) and Title 49 CFR code (DHS-TSA).*

Additional standards and guidance used by the Authority can be found in the FAA Advisory Circular 150 series. The Authority also operates the Airports under the state and local regulations pertaining to stormwater runoff, wetland protection, zoning, labor requirements, wage rates, working hours, and noise ordinances.

FIGURE 2-2 AIRPORT MANAGEMENT ORGANIZATIONAL CHART



3 AIRFIELD FACILITIES

This section summarizes existing airfield facilities at the Airport. These facilities include runways, taxiways, apron areas, and navigational aids. The existing layout of the airfield is shown in **Figure 3-1** and the airport layout plan is displayed in **Appendix A** of this report.

3.1 RUNWAY SYSTEM

The existing runway configuration at VQS consists of a single runway, designated Runway 9-27. Runway 9-27 is a 4,301-foot long by 75-foot-wide asphalt runway and is oriented in an east/west direction. The runway's surface is in good condition, and it has basic markings which are in good condition. The runway has a weight bearing capacity of 20,000 lbs. for single wheel and 40,000 lbs. for double wheel aircraft. PRPA recently made improvements to the runway pavement including new pavement markings, resurfacing and drainage improvements.

Table 3-1 provides detailed information on the Airport's runway system and **Appendix D** of this report, contains the Airport Master Record, FAA Form 5010-1.

TABLE 3-1
RUNWAY CHARCTERISTICS

Characteristic		Runway	y 9-27		
Length (ft.)		4,30	4,301		
Width (ft.)		75	5		
Runway Surface	Туре	Asph	nalt		
Runway Surface	Condition	God	od		
Runway Surface	Treatment	-			
Load Bearing Single Wheel		20,0	20,000		
Capacity (lbs)	Dual Wheel	40,0	40,000		
Runway Edge Lig	ght Intensity	Medium I	Medium Intensity		
Runway End		9	27		
Markings/Condi	tion	NPI/Good	Basic/Good		
Visual Glide Slope Indicator		No	No		
Displaced Threshold		896 ft	No		
Runway End Indicator Lights		No	No		
Approach Lights		No	No		

Source: FAA Form 5010-1: Airport Master Record, Accessed June 2021; PRPA, 2021

FIGURE 3-1 VQS AIRFIELD LAYOUT



Antonio Rivera Rodriguez Airport (VQS)`

3.1.1 Declared Distances

Declared distances identify different lengths of runway pavement available for various aircraft operations due to different circumstances. The declared distances at VQS equal the full extent of the runway pavement for Takeoff Run Available (TORA) and Takeoff Distance Available (TODA) but are decreased for Landing Distance Available (LDA) and Accelerate Stop Distance Available (ASDA). The declared distances of VOS are shown in **Table 3-2.**

TABLE 3-2
DECLARED DISTANCES

Runway	TORA (ft.)	TODA (ft.)	ASDA (ft.)	LDA (ft.)
9	4,301	4,301	4,301	3,405
27	4,301	4,301	4,094	3,405

Source: FAA Form 5010-1: Airport Master Record, Accessed June 2021; PRPA, 2021

3.1.2 Pavement Condition

In 2016, PRPA executed a Regional Airport Pavement Maintenance and Management Plan (RAPMMP) for all pavements within any of the publicly owned airports in Puerto Rico. As a result, PRPA completed a pavement maintenance management program report for VQS with a visual condition survey inspection for each of the airfield's areas. Within the report, each of the inspected airfield areas had a Pavement Condition Index (PCI) calculated, using guidance from *FAA Advisory Circular 150/5380-7B, Airport Pavement Management Program (PMP)*. The purpose of a PCI value is to reflect the structural integrity and surface operational condition of each area of pavement inspected. VQS's PMP concluded that based on ASTM D 5340-12, the airside facilities of VQS had an overall area-weighted PCI average of 59, which represents a fair overall condition for its airfield network.⁵

PRPA is in the process of rehabilitation the runway pavement though a major reconstruction program. The project is expected to be complete during the first half in 2022.

The pavement of Runway 9-27 is composed of Asphalt Concrete (AC). It was last initially constructed in 1966 and extended in 1992 and 1998. Runway 9-27 received a weighted average PCI rating ranging between 65-72 (or fair to satisfactory) for each of the separate areas investigated in the VQS PMP.

The overall 2016 PCI map from the PMMP is included in **Appendix C**.

Appendix E contains photos of the current runway condition from the site visit conducted for this assessment.

3.2 TAXIWAY SYSTEM

VQS has a total of eight taxiways the provide access around the airfield. Taxiway A is a full-length parallel taxiway and the main taxiway at VQS. Its length equals that of the runway at 4,301 feet and it is 35 feet

⁵ Kimley Horn and Associates, Inc. (2016) *Regional Airports Pavement Maintenance and Management Program, Antonio Rivera Rodriquez Airport (VQS)*

wide. It is connected to each of the connector taxiways and is adjacent to the Main Apron. Taxiway A is constructed out of AC pavement, and as of the 2016 VQS PMP, the four inspected areas of Taxiway A had PCI ratings that ranged from fair to very poor.

Taxiway B is 45 feet wide and constructed of AC pavement. It is a connector taxiway that begins at the Runway 27 threshold and extends south for 225 feet to Taxiway A. As of the 2016 VQS PMP, the inspection of Taxiway B had a PCI rating of very poor.

Taxiway C is 40 feet wide and constructed of AC pavement. It is an angled connector taxiway that begins approximately 500 feet west of the of the Runway 27 threshold and extends to the south for a distance of approximately 275 feet intersecting with Taxiway A and the Main Apron. As of the 2016 VQS PMP, the inspection of Taxiway C had a PCI rating of serious.

Taxiway D is 35 feet wide and constructed of AC pavement. It is a connector taxiway that begins approximately 1,000 feet west of the Runway 27 threshold and extends to the south for approximately 225 feet where it intersects with Taxiway A. Taxiway D, continues south of Taxiway A for another 75 feet where it intersects with the general aviation (GA) Apron. As of the 2016 VQS PMP, the inspection of Taxiway D had a PCI rating of very poor.

Taxiway D1 is approximately 35 feet wide and constructed of AC pavement. It is a connector taxiway that provides access from the GA Apron to Taxiway A. It is located south of Taxiway A, in between Taxiway D and C. Taxiway D1 extends from Taxiway A to the south for approximately 75 feet where it intersects with the GA Apron. As of the 2016 VQS PMP, the inspection of Taxiway D1 had a PCI rating of very poor.

Taxiway E is approximately 55 feet wide and constructed of AC pavement. It is a connector taxiway that begins approximately 1,600 feet east of the Runway 9 displaced threshold and extends to the south for approximately 240 feet where it intersects with Taxiway A. As of the 2016 VQS PMP, the inspection of Taxiway E had a PCI rating of satisfactory.

Taxiway F is approximately 50 feet wide and constructed of AC pavement. It is a connector taxiway that begins approximately 700 feet east of the Runway 9 displaced threshold and extends to the south for approximately 240 feet where it intersects with Taxiway A. As of the 2016 VQS PMP, the inspection of Taxiway F had a PCI rating of fair.

Taxiway G is 40 feet wide and constructed of AC pavement. It is a connector taxiway that begins at the Runway 9 end and extends to the south for approximately 240 feet where it intersects with Taxiway A. As of the 2016 VQS PMP, the inspection of Taxiway G had a PCI rating of very poor.

Table 3-3 provides detailed information on the Airport's taxiway system

TABLE 3-3
TAXIWAY CHARACTERISTICS

Characteristic -	Taxiway			
Characteristic	Α	В	С	D
Width (ft.)	35	45	40	35
Surface Type	AC	AC	AC	AC
Pavement Condition (PCI)	27-79	34	24	39,48
Lighting	MITL	MITL	MITL	MITL
Characteristic -	Taxiway			
Characteristic	D1	E	F	G
Width (ft.)	35	55	50	40
Surface Type	AC	AC	AC	AC
Pavement Condition	28	73	59	39
Lighting	MITL	MITL	MITL	MITL

Source: PRPA RAPMMP, Antonio Rivera Rodriguez Airport (VQS), 2016

3.3 APRONS

The Airport has two identified aprons that provide areas for aircraft parking, loading, unloading, maintenance and fueling. The GA apron is the larger of the two, and services the GA aircraft. The GA Apron is located south of runway and Taxiway A on the east end of the Airport, just west of the passenger terminal building. The apron has an area of 116,561 square feet and is connected to the airfield by Taxiways D and D1. The fuel farm is centrally located on the southern edge of the apron, and there is also an Air Vieques maintenance hangar on its western edge. The 2016 VQS PMP notes that the GA Apron was constructed in 1988 and 1994 out of AC pavement. As of the 2016 VQS PMP, the apron had a PCI rating of poor in both sections.

The slightly smaller Main Apron has an area of 95,676 square feet and is located adjacent to the GA Apron to its west. It is connected to the airfield by Taxiways A, B, and C. The 2016 VQS PMP notes that the Main Apron was last constructed in 1989 and is made of AC pavement. As of the 2016 VQS PMP, the Main Apron had a PCI rating that ranged from satisfactory to good.

Table 3-4 provides a summary of the two aprons by usage and the total approximate apron area at VQS and **Figure 3-1** displays the apron areas at the Airport.

TABLE 3-4
APRON CHARACTERISTICS

Apron Type (By usage)	Pavement Condition (PCI)	Total Combined Apron Area (square feet)
GA Apron	44, 54	116,561
Main Apron	43	95,676

Source: PRPA RAPMMP, Antonio Rivera Rodriguez Airport (VQS), 2016

3.4 NAVIGATIONAL AIDS

Navigational Aids (NAVAIDs) are electronic, visual, and meteorological air navigation equipment that facilitate flight operations at an airport. Visual aids include airfield lighting, which enhance flight safety during instances of inclement weather and/or darkness. Electronic aids are devices used for aircraft instrument approaches. Meteorological aids provide an airport with real time weather updates for air traffic control personnel and pilots. VQS provides visual NAVAIDs, but there are no electronic or meteorological NAVAIDs.

There are multiple visual NAVAIDs at VQS including an airport rotating beacon, wind cone, various lighting aids, and signage. There is also a four light Precision Approach Path Indicators (PAPI) found on the north side of Runway 9. Airfield lighting is vital to the airport as it assists pilots with navigating in and around the airport. It enhances accessibility for pilots during periods of darkness and/or poor visibility. There is medium intensity runway lighting (MIRL) and threshold/runway end lights on both runway ends. The threshold/runway end lights are two sided colored lights, with the green side for recognition of the threshold of a runway for aircraft on an approach, and the red side for recognition of the end of a runway for aircraft on a departure. The taxiway system is equipped with medium intensity taxiway lighting (MITL) along the pavement edge.

Table 3-5 identifies the navigational aids found at the Airport. **Figure 3-1** highlights the various NAVAIDs found at the Airport.

TABLE 3-5 NAVAIDS

Electronic NAVAIDs	Runway 9	Runway 27
VOR	-	-
Glideslope	-	-
Localizer	-	-
Visual NAVAIDs	Runway 9	Runway 27
Airport Rotating Beacon (APBN)	Ye	es
Medium Intensity Runway Lights (MIRLs)	Yes	Yes
Runway End Identifier Lights (REILs)	-	-
Threshold/Runway End Lights	Yes	Yes
Precision Approach Path Indicator (PAPI)	Yes	-
Segmented Circle and Wind Cone	-	Yes
Wind Cone	-	-
Meteorological NAVAIDs	Runway 9	Runway 27
ASOS	-	-
AWOS	-	-

Source: AirNAV, 2021

In 2022, PRPA installed new airfield lighting and signage, a new airport beacon and windsocks, and a new concrete electric vault and emergency generator at the Airport.

4 PASSENGER TERMINAL FACILITIES

4.1 GENERAL INFORMATION

The Airport's passenger terminal is located on the north side of the Airport along Highway 22. The two-story facility is approximately 13,000 square feet. The Airport's terminal, landside, and tenant facilities are outlined in **Figure 4-1**.

4.2 AIRCRAFT PARKING POSITIONS AND GATES

The terminal apron has marked spaces for six passenger aircraft which are all ground loaded. The gate positions are sized for ADG I aircraft (wingspans up 49 feet) to be simultaneously parked.

4.3 TERMINAL BUILDING OVERVIEW

The terminal building is approximately 13,000 square feet in size across two stories. The lower level includes airline check-in and baggage claim. The second story has offices for various airport functions including the Airport manager's office, a Tourism Information Center, and a recently remodeled bathroom. However, the second-floor experienced damage from Hurricane Maria in 2017. In 2022 PRPA made major repairs and improvements to the passenger terminal from the damage caused to the Hurricane.

The Tourism Information Center provides assistance to passengers and the surrounding neighborhoods including calling and arranging transportation, organizing, and arranging tours, and other recreational and tourist activities for the island.

Air carrier check-in is provided in two locations: inside the terminal building and a secondary building to the east. The secondary location provides check-in for Vieques Air Link while all other carriers are within the terminal building.

The terminal building contains a single holdroom with one door with access to the terminal ramp for enplaning and deplaning passengers to board the aircraft. The check-in area for Vieques Air Link also has additional seating but does not currently provide direct access to the ramp.

There is a baggage claim unit that is occasionally used by Cape Air. All other air carriers do not use the dedicated baggage facilities.

There are currently no concessions available inside the terminal building. There is a small café located just outside to the southwest of the terminal building.

THERE ARE NO PASSENGER SCREENING SERVICES AT THE AIRPORT. THE TERMINAL LAYOUT IS SHOWN IN FIGURE 4-2 AND FIGURE 4-3 AND FIGURE 4-4 SHOWS THE ADMINISTRATIVE SPACE CURRENTLY DESIGNATED FOR AND OPERATED BY PRPA WITHIN THE AIRPORT TERMINAL. THE PASSENGER TERMINAL SUFFERED MAJOR DAMAGE BY HURRICANE MARIA AND NEEDED MAJOR REPAIRS. PRPA IS IN THE PROCESS OF COMPLETING THESE REPAIRS. FIGURE 4-1

VQS LANDSIDE AND TENANT FACILITIES





Antonio Rivera Rodgriquez Airport (VQS)



Source: RS&H, Inc., 2021

FIGURE 4-2 TERMINAL LAYOUT PLAN LEVEL 1






FIGURE 4-3 TERMINAL LAYOUT PLAN LEVEL 2



Edificio terminal, segundo nivel

FIGURE 4-4 TERMINAL ADMINISTRATIVE SPACE

TERMINAL VIEQUES - AREA 400 P.C.



5 LANDSIDE FACILITIES

This section describes the airport access roadways system, including off-airport and on-airport roadways, terminal curbside areas, public and employee parking facilities, and rental car facilities.

5.1 REGIONAL ROADWAY CONNECTIVITY

Roadway access to the passenger terminal building and parking lots is available by way of Highway 200. Highway 200 is a main thoroughfare to the main population center approximately four miles to the east in Santa Maria.

5.2 AIRPORT ACCESS ROADWAY SYSTEM

Airport facilities are located on the south side of the Airport and accessed directly from Highway 200. Highway 200 is a two-lane two-way road connecting the airport to Santa Maria. There are no on-airport roadways.

5.3 TERMINAL CURBFRONT

The terminal curbfront consists of a one lane one-way unmarked road off of Highway 200. The terminal curbfront is approximately 75 feet long and runs directly in front of the main terminal building and the Viegues Air Link facility.

5.4 COMMERCIAL VEHICLE AND RENTAL CAR FACILITIES

There are no commercial or rental cars available at the Airport. The Tourism Information Center located on the second floor of the terminal building can call taxis for passengers.

5.5 PUBLIC PARKING FACILITIES

The Airport has one general public parking lot for all passengers and employees to the southwest of the terminal building. The public parking lot is approximately a 36,000-sf paved asphalt surface with an approximate capacity of 75 vehicle parking spaces.

6 TENANT FACILITIES

6.1 CARGO FACILITIES

There are no dedicated cargo facilities at the Airport.

6.2 GENERAL AVIATION FACILITIES

The general aviation ramp is to the west of the air carrier apron. It has a ramp capacity of approximately 12 single-engine piston aircraft. There is no separate general aviation terminal building.

6.3 OTHER TENANT FACILITIES

There is one major tenant at the Airport. Vieques Air Link has a maintenance facility and hangar to the west of the general aviation ramp. The hangar is approximately 9,000 square feet and houses multiple aircraft undergoing maintenance.

Table 6-1 provides a list of tenants at the Airport. Tenants at VQS are constantly evolving with the construction of new contracts/tenants, the renewal of existing contracts, or the expiration of terminating contracts. The list of tenants provided below is from a snapshot in time and may not accurately reflect the existing conditions.

TABLE 6-1 TENANT ACTIVITY

Lessee	Term of Contract	Date Signed	Contract Expiration Date	Object of the Lease
Air Sunshine International, Inc.	5 yrs.	20-Apr-2018	19-Apr-2023	Counter space/Office space
Air America, Inc.	5 yrs.	02-May-2017	01-May-2022	Counter in Terminal Bldg.
Air Charter, Inc. h/n/c Air Flamenco	10 yrs.	06-Jun-2018	05-Jun-2028	
Tourism Company	5 yrs.	16-Dec-2016	30-Nov-2021	
Green Horizon, Inc.	6 months	24-Jun-2016	23-Dec-2016	
Hyannis Air Services, Inc. dba Cape Air	1 yr.	11-Apr-2014	20-Jul-2015	
Isla Nena Café, LLC	5 yrs.	07-Aug-2008	06-Aug-2013	
JJC Exterminating Corp.	6 months	30-Aug-2016	30-Mar-2017	
M & N Aviation	5 yrs.	03-Nov-2014	2-Nov-2019	
Maritza's Car Rental, Inc	3 yrs.	22-May-2015	29-May-2018	
Puerto Rico Aircraft Leasing Corp. H/N/c Taxi Aéreo	5 yrs.	08-Jun-2017	07-Jun-2022	
Reig Aviation Services, Inc.	11 yrs.	23-Feb-2017	31-Dec-2028	
US Custom and Border Protection	1 yr.	30-Nov-1994	29-Nov-1995	
US Department of Agriculture Animal and Plant Health Inspection Service Plant Protection and Quarantine	5 yrs.	01-Aug-2014	31-Jul-2019	
Vieques Air Link, Inc.	4 yrs.	30-Aug-2016	25-Aug-2020	
Vision Green, Inc. dba Island Jeep Rental	5 yrs.	30-Dec-2016	29-Dec-2021	

Source: PRPA, 2021

Note: Red text identifies expired contracts

7 AIRPORT SUPPORT FACILITIES

7.1 AIRPORT TRAFFIC CONTROL TOWER

There is no airport traffic control tower at the airport.

7.2 AIRCRAFT RESCUE AND FIRE-FIGHTING FACILITIES

The Aircraft Rescue and Firefighting (ARFF) involves hazard mitigation, as well as fire prevention, fire fighting, rescue, and medical response in the event of an aircraft incident or accident. All Part 139 airports serving scheduled and unscheduled air carriers are required to provide ARFF services at an appropriate level.

VQS has a dedicated and staffed ARFF facility located to the west of the passenger terminal building. The facility has three vehicle bays. The ARFF facility is approximately 3,000 square feet with offices and support areas next to the garage which total an approximate 1,700 square feet space.



Source: RS&H, Inc., 2019

7.3 AIRPORT MAINTENANCE FACILITIES

Airport maintenance does not have a dedicated facility.

7.4 AIRCRAFT FUELING FACILITIES

There are three gas tanks at the Airport. However, the tanks are not operational at this time. PRPA notes that they could become operational again if repaired. The tanks were decommissioned after non-use.

7.5 ADDITIONAL AIRPORT DEVELOPABLE AREAS

There are no areas for development on airport property.

8 AVIATION ACTIVITY SUMMARY

This section presents historic and available projections of aviation activity at the Airport. The sections presenting historic aviation activity focus on enplaned passengers (number of passengers boarding commercial service and chartered flights), aircraft operations (landings and take-offs by aircraft), and based aircraft (those aircraft permanently stored at the Airport). There is also a review of seven years of historic cargo activity represented in total pounds enplaned and deplaned at VQS.

The PRPA generally reports its passenger numbers and other airport related statistics for its fiscal year (FY) which runs from July 1 to June 30, as such all airport statistics included in this section of the report are shown for the Puerto Rico fiscal year.

Projections of aviation activity at the Airport into the future were not developed specifically for this report. Projections shown in this section are taken from the FAA's Terminal Area Forecast (TAF) 2022 published in March 2023.

8.1 HISTORIC AVIATION ACTIVITY

8.1.1 Passenger Activity

Historically, enplanements at VQS have been relatively consistent with a peak of 87,846 in 2006. Since that time through 2017, enplanements have been between 70,000 and 77,000 annually. While VQS still represents the third most enplanements of the nine airports being assessed, it has decreased at an annual rate of -8% from 2011-2019, and then again by -26% from 2019 to 2021 as a result of the worldwide COVID-19 pandemic (or Public Health Emergency). Enplanements have rebounded to just above prepandemic levels with 46,729 recorded enplanements in 2022.

The second column in **Table 8-1** provides the historic enplanement totals from 2001 to 2022.

8.1.2 Air Service

Commercial passenger air carrier operations are identified as "air carrier" or "commuter and air taxi". The definition for the distinction between the two categories is the seating capacity. An air carrier aircraft is one that carries 60 passengers or more. Air service to VQS is provided from SIG, RVR and CPX by Vieques Air Link, Flamengo, Seaborne and Cape Air.

Historically, air taxi/commuter operations at VQS were fairly stable from 2001 to 2004 with approximately 26,179 operations annually. Air carrier operations at VQS since 2013 have been between 8,000 and 8,100 operations annually.

8.1.3 Aircraft Operations

An aircraft operation is defined as either a takeoff or a landing. Airfield activity at an airport is measured and forecast according to annual aircraft operations. Historically, VQS has experienced steady and increasing aircraft operations. Peak operations over the past 20 years occurred in 2013 with 37,000 and has remained steady at 30,000 operations or more from 2013-2017, at which time the annual operations

dropped to 20,000 for two consecutive years, before dropping further to 18,424 operations in 2020. Annual operations have surpassed 2019 levels recording 25,032 in 2022.

The third column in **Table 8-1** presents historical annual aircraft operations from 2001-2022.

8.1.4 Based Aircraft

A based aircraft is defined as any aircraft that is operational and airworthy, and based (or located) at a particular facility for a majority of the year. In 2001, VQS had 33 or more based aircraft from 2002-2005. It then decreased to only four in the 2013-2016 period. Recently, the Airport has made a strong recovery sustaining 33 based aircraft since 2017.

The fourth column in **Table 8-1** provides the based aircraft totals from 2001 to 2022.

8.1.5 Cargo Activity

The cargo activity review was limited to seven years from 2016-2022. The Airport has sustained strong cargo activity during that time with an average of over 1,000,000 pounds of cargo being processed from 2016-2022. During that time, the cargo activity at VQS continued to increase, and never showed a decline despite the Public Health Emergency and reached 1,338,533 pounds processed in 2022.

The last column in **Table 8-1** provides PRPA total cargo in pounds from 2001 to 2022.

TABLE 8-1
HISTORIC - VOS AIRPORT STATISTICS

Fiscal Year	Enplanements	Operations	Based Aircraft	Cargo (lbs.)
2001	56,597	26,842	22	Cargo (ibs.)
2002	51,950	24,358	34	
2003	52,417	23,510	33	
2004	55,673	25,130	34	
2005	79,113	32,242	34	
2006	87,846	36,192	34	
2007	82,050	33,394	18	
2008	84,484	32,376	18	
2009	74,234	31,674	19	
2010	74,177	34,220	19	
2011	76,957	34,594	19	
2012	75,841	36,280	15	
2013	73,370	36,669	4	
2014	76,643	34,653	4	
2015	79,894	33,890	4	
2016	72,170	34,668	4	784,060
2017	65,017	31,822	33	851,035
2018	35,793	20,270	33	1,014,662
2019	42,085	22,978	33	1,095,774

2020	32,700	18,424	33	1,103,182
2021	31,203	19,278	33	1,454,265
2022	46.729	25.032	33	1.338.533

Source: PRPA Records; FAA TAF 2022; FAA 5010-1 Form, 2022

8.2 FUTURE AVIATION ACTIVITY PROJECTIONS

This section provides the FAA derived forecast identified as the FAA TAF 2022. The FAA TAF is an annual forecast prepared by the FAA and includes projections of operations by type, based aircraft counts, and projections of enplanements. The FAA TAF 2022 published by the FAA in March 2023 was used for the forecast of aviation activity from 2022-2042⁶. The cargo activity forecast for VQS was developed using historical trends from 2016-2022.

Table 8-2 shows the forecast of aviation activity for VQS from 2022-2042.

TABLE 8-2 AVIATION FORECASTS - VQS (2022-2042)

Fiscal Year	Enplanements	Operations	Based Aircraft	Cargo (lbs.)		
2022	46,729	25,032	33	1,338,533		
Forecast						
2023	46,729	30,898	33	1,434,518		
2024	46,729	30,898	33	1,537,386		
2025	46,729	30,898	33	1,647,631		
2026	46,729	30,898	33	1,765,781		
2027	46,729	30,898	33	1,892,403		
2028	46,729	30,898	33	2,028,106		
2029	46,729	30,898	33	2,173,539		
2030	46,729	30,898	33	2,249,613		
2031	46,729	30,898	33	2,328,350		
2032	46,729	30,898	33	2,409,842		
2033	46,729	30,898	33	2,494,187		
2034	46,729	30,898	33	2,581,483		
2035	46,729	30,898	33	2,671,835		
2036	46,729	30,898	33	2,765,349		
2037	46,729	30,898	33	2,862,136		
2038	46,729	30,898	33	2,962,311		
2039	46,729	30,898	33	3,065,992		
2040	46,729	30,898	33	3,173,302		
2041	46,729	30,898	33	3,284,367		
2042	46,729	30,898	33	3,399,320		
Annual Growth Rate						

⁶ While the growth rate for the 2022-2042 projections was used for annual enplanements, operations, and based aircraft, the 2022 totals varied in some instances where PRPA records showed differences. As a result, these totals were sometimes carried forward in forecasts that had no growth shown in the FAA TAF 2022, but still may be referenced as the FAA TAF 2022 Forecast.

2022-2032	0.0%	2.1%	0.0%	6.1%
2032-2042	0.0%	0.0%	0.0%	3.5%
2022-2042	0.0%	1.1%	0.0%	4.8%


Source: FAA TAF 2022; RS&H 2023

8.2.1 Passenger Activity

Passenger activity at VQS is projected to remain constant at 43,753 over the forecast horizon.

Figure 8-1 displays the passenger enplanement forecast from 2022-2042.

FIGURE 8-1
ENPLANED PASSENGER FORECAST (2022-2042)




Sources: FAA TAF 2022; PRPA Records

8.2.2 Aircraft Operations

According to the FAA TAF 2022, the total annual operations are projected to remain steady at VQS with 30,898 operations through 2042.

Figure 8-2 displays the total annual operations forecast from 2022-2042.

FIGURE 8-2 OPERATIONS FORECAST (2022-2042)




Sources: FAA TAF 2022; PRPA Records

8.2.3 Based Aircraft

Based aircraft are assumed to remain constant over the forecast horizon, sustaining a total of 33 based aircraft.

Figure 8-3 displays the based aircraft forecast from 2022-2042.

FIGURE 8-3 BASED AIRCRAFT FORECAST (2022-2042)




Sources: FAA TAF 2022; PRPA Records

8.2.4 Cargo Activity

Since 2016, the Airport has shown continued cargo growth. As a result, cargo is projected to increase at a 6.1 percent annual rate until 2030 and then reduce its high growth rate to a more moderate increase of 3.5 percent until 2042. By 2042, the Airport will process almost 3,400,000 pounds of cargo annually.

Figure 8-4 displays the cargo forecast from 2022-2042.

FIGURE 8-4 CARGO FORECAST (2022-2042)



Sources: RS&H 2023; PRPA Records

9 CAPITAL IMPROVEMENT PROGRAM

This section presents the current Airport Capital Improvement Program (ACIP) for the Airport identifying capital projects that will be undertaken through 2027. Projects listed in the ACIP for VQS were provided by the PRPA.⁷

9.1 CURRENT ACIP SUMMARY

Table 9-1 presents a summary of the current 5-year ACIP for the Airport, including the estimated cost and eligible funding sources.

TABLE 9-1
AIRPORT CAPITAL IMPROVEMENT PROGRAM AND FUNDING SOURCES (\$000)

Project Description	Cost	Federal Funding	PRPA	Start FY	End FY
Airfield Pavement Rehabilitation	\$500	runding	\$500	2023	2024
Construction Runway Connectors and Visual Aids	\$13,350	\$13,000	\$250	2021	2023
Construction	\$11,100	\$11,100	\$0	2021	2023
Construction Management	\$2,000	\$2,000	\$0	2022	2023
Contingency	\$250 \$0		\$0	2022	2023
Hurricane Maria Damage Repairs	\$1,700	\$1,700	\$0	2023	2023
Terminal Repairs	\$2,300	\$1,890	\$410	2020	2023
Construction	\$2,000	\$1,800	\$200	2021	2023
Inspection	\$100	\$90	\$10	2021	2023
Contingency	\$200		\$200	2020	2023
Parking Pavement Rehabilitation	\$150		\$150	2023	2023
ARFF Equipment Acquisition	\$50		\$50	2023	2023
Subtotal	\$18,050	\$16,590	\$1,460		

Source: Puerto Rico Ports Authority, 2023; RS&H, 2023 Notes: All costs shown in thousands of U.S. Dollars

Total 5-year ACIP project costs are estimated to be over \$18 million through the 2027 time period. A total of 91.4 percent of the funding is anticipated through FAA grants with the remaining 16 percent from PRPA funds or have already been incurred.

9.2 BIPARTISAN INFRASTRUCTURE BILL


The Bipartisan Infrastructure Law (BIL) provides \$15 billion for airport-related projects as defined under the existing Airport Improvement Grant and Passenger Facility Charge criteria. The money can be invested in runways, taxiways, safety, and sustainability projects, as well as terminal, airport-transit connections, and roadway projects.

⁷ The VQS CIP was provided in May 2023.

For FAA fiscal year 2023 the Airport will receive \$1,023,708. This total is subject to change during the next three years based on the Airport's enplanement and cargo totals.

_

APPENDIX A AIRPORT LAYOUT PLAN



Source: PRPA, 1998

APPENDIX B FEMA REPAIRS

Antonio Rivera Rodriguez Airport (VQS)

Site Inspection				Antonio Rivera Rodriguez Airpor	Compl	eted	O	n-Going		Not Sta	rted	
Site Inspection Date	Damage Date	Description	Area Affected	Damage	Yes/No	Date	Yes/No	Completion Date	Responsible Party	Start Date	Project Duration	Project Cost
Air Rescue Building												
					No		No		FEMA			
		On September the 20th 2017, Hurricane Maria's wind and rain caused subsequent damages and flooding to Antonio Rivera	Exterior	Damaged rolling doors: (14'-0" x 15'-0") x 2 Damaged rolling door: (12'-0" x 15'-0")	No		No		FEMA	TBD TBD	TBD TBD	TBD TBD
10/20/2018	9/20/2017	Rodriquez Airport Main Terminal and the associated facilities. Antonio Rivera Rodriquez Airport is composed of the		Damaged aluminum accordion window shutters: (28'-0" x 5'-0") Damaged double hung windows: (6'-0" x 4'-0") x 9	No No		No No		FEMA FEMA	TBD TBD	TBD TBD	TBD TBD
		following: Main Terminal Building, Building #1, Air Rescue Building, Hanger #1, and Runway.		Damaged acoustic ceiling tiles: (5'-0" x 68'-0") Damaged plaster ceiling in bathrooms: (17'-0" x 18'-0") Damaged wall security lighting: 6 EA.	No No No		No No No		FEMA FEMA FEMA	TBD TBD TBD	TBD TBD TBD	TBD TBD TBD
				Damaged HID 250 watt light fixtures: 3 EA. Painted wall surfaces in garage damaged: (220'-0" x 24'-0") Modified bitumen roofing damaged: ((60'-0 x 32'-0") + (1/2 (50'-0" x 31'-	No No		No No		FEMA FEMA	TBD TBD	TBD TBD	TBD TBD
			Roof	4") + (10'-0" × 19'-4") + (23'-0" × 68'-0"))	No		No		FEMA	TBD	TBD	TBD
			W Lounge									
	9/20/2017	On September the 20th 2017, Hurricane Maria's wind and rain caused subsequent damages and flooding to Antonio Rivera Rodriquez Airport Main Terminal and the associated facilities. Antonio Rivera Rodriquez Airport is composed of the following: Main Terminal Building, Building	Interior	Suspended ceiling tiles damaged (both side of breezeway): (100′-0″ x 30′-0″) x 2	No		No		FEMA	TBD	TBD	TBD
10/20/2018				Concrete wall and drywall damaged all interior wall (Finish and Paint): ((30'-0" x 8'-0") x 2) + ((40'-0" + 30-0") x 2'-0"))	No		No		FEMA	TBD	TBD	TBD
				One metal and glass double door damaged: (6'-0" x 7'-0")	No		No		FEMA	TBD	TBD	TBD
		#1, Air Rescue Building, Hanger #1, and		One glass panel (side glass) damaged: (4'-0" x 5'-0")	No		No		FEMA	TBD	TBD	TBD
		Runway.		One transom glass panel damaged: (2'-0" x 6'-0")	No		No		FEMA	TBD TBD	TBD TBD	TBD
				One glass panel damaged: (4'-0" x 5'-0") One glass panel damaged: (1'-0" x 4'-0")	No No		No No		FEMA FEMA	TBD	TBD	TBD TBD
				Mold remediation of entire structure: (43'-0" x 30'-0") x 2	No		No		FEMA	TBD	TBD	TBD
			Roof	Roll bituminous roof damaged: (100'-0" x 30'-0")	No		No		FEMA	TBD	TBD	TBD
		Air Link	Hangar and Sto		110		110		7 2 17 17		100	100
					No		No		FEMA			
		0 - C		Damaged hanger doors: (20'-0" x 18'-0") x 4						TBD	TBD	TBD
		On September the 20th 2017, Hurricane Maria's wind and rain caused subsequent		Damaged corrugated metal roofing: (100'-0" x 90'-0")	No		No		FEMA	TBD	TBD	TBD
		damages and flooding to Antonio Rivera		Damaged purlins (25'-0"): 24 EA.	No		No		FEMA	TBD	TBD	TBD
10/20/2018	9/20/2017	Rodriquez Airport Main Terminal and the associated facilities. Antonio Rivera		Damaged corrugated translucent panels: (18'-0" x 4'-0") x 8 Damaged corrugated metal siding: ((12'-0" x 20'-0") + (10'-0" x 20'-0"))	No No		No No		FEMA FEMA	TBD TBD	TBD TBD	TBD TBD
	-, -5, 2517	Rodriquez Airport is composed of the		Damaged metal roof vents: (12'-0" x 4'-0") x 4	No		No		FEMA	TBD	TBD	TBD
		following: Main Terminal Building, Building		Damaged structural beam: (80'-0" x 2'-0")	No		No		FEMA	TBD	TBD	TBD
		#1, Air Rescue Building, Hanger #1, and		Damaged structural column: (25'-0" x 2'-0")	No		No		FEMA	TBD	TBD	TBD
		Runway.		Damaged louvered windows: (3'-0" x 4'-0") x 32	No		No		FEMA	TBD	TBD	TBD
				Damage metal door: (3'-0" x 7'-0")	No		No No		FEMA	TBD TBD	TBD TBD	TBD TBD
				Damaged halide pendant light fixtures: 16 (150 Watt) Damaged modified bitumen roofing: (90'-0" x 20'-0")	No No		No No		FEMA FEMA	TBD	LBD	TBD
				Mold remediation: (90'-0" x 20'-0")	No		No		FEMA	TBD	TBD	TBD
			VAL Storage	Damaged finished wall and ceiling surface: ((90'-0" x 20'-0") + (90'-0" x 8'-0" x 2) + (20'-0" x 8'-0" x 2))	No		No		FEMA	TBD	TBD	TBD

Antonio Rivera Rodriguez Airport (VQS)

Antonio Rivera Rodriguez Airport (VQS)

Antonio Rivera Rodriguez Airport (VQS)												
Site Inspection						leted	0	n-Going		Not Sta	rted	
Date	Damage Date	amage Date Description Area Affected Dama		Damage	Yes/No	Date	Yes/No	Completion Date	Responsible Party	Start Date	Project Duration	Project Cost
				Main Terminal								
				Corrugated metal canopies panels damaged: (7'-0" x 125-0") + (31'-0" x 31'-0") + (30'-0" x 7'-6") + ((30'-0" x 16'-0") x	No		No		FEMA	02.2040	700	T00
				2) +(10'-0" x 24'-0") Corrugated metal roof panels:						Q3 2019	TBD	TBD
				(((((31'-6" + 20'-0") / 2) x 10'-0") x 6) + ((((31'-6" + 11'-0") / 2) x 28'-0") x 2)	No		No		FEMA	Q3 2019	TBD	TBD
				Corrugated metal roof panels (peak):	No		No		FEMA	02.2040	TOD	TOD
				((31'-6" x 15'-9") / 2) x 4 Metal and Glass fixed windows damages: 4 (5'-0" x 3'-0")	No		No		FEMA	Q3 2019 Q3 2019	TBD TBD	TBD TBD
				Corrugated metal flashing damaged 1'-0" wide: (36'-0" + 81'-0" + 25'-0")	No		No		FEMA			
			Exterior	+ (31'-6" x 8)					***************************************	Q3 2019	TBD	TBD
			Façade	Metal gutters damaged 5": (36'-0" + 81'-0" + 25'-0") + (31'-6" x 8)	No		No		FEMA	Q3 2019	TBD	TBD
				Corrugated translucent fiberglass walkway panels damaged: (12'-0" x 4'-0") x 8	No		No		FEMA	Q3 2019	TBD	TBD
				Walkway security fencing damaged metal mesh and frame: (90'-0" x 5'-	No		No		FEMA	Q3 2019	TBD	TBD
				Metal security fencing on retaining walls: (80'-0" x 3'-0")	No		No		FEMA	Q3 2019	TBD	TBD
		On September the 20th 2017, Hurricane Maria's wind and rain caused subsequent damages and flooding to Antonio Rivera Rodriquez Airport Main Terminal and the associated facilities. Antonio Rivera Rodriquez Airport is composed of the following: Main Terminal Building, Building		Metal electric sliding door damaged: (6'-0" x 7'-0") x 3	No		No		FEMA	Q3 2019	TBD	TBD
				Metal door first and second floor with openers damaged: $(3'-0'' \times 7'-0'') \times 6$	No		No		FEMA	Q3 2019	TBD	TBD
				Metal and tempered safety glass side window damaged: (34'-0" x 7'-0")	No		No		FEMA	Q3 2019	TBD	TBD
				Aluminum sliding louvers damaged: Second Floor Operations: (34'-0" x 7'-0")	No		No		FEMA	Q3 2019	TBD	TBD
				Exterior Halide light wall fixtures (Walkway): (200 watt) x 2	No		No		FEMA	Q3 2019	TBD	TBD
10/20/2018	9/20/2017			Damaged exterior wall painted surfaces: 6720 SQ. FT.	No		No		FEMA	Q3 2019	TBD	TBD
10,20,2010	l F			Northern entrance suspended ceiling tiles damaged: $(2'-0'' \times 2'-0'') \times (34'-0'' \times 30'-0'')$	No		No		FEMA	Q3 2019	TBD	TBD
		#1, Air Rescue Building, Hanger #1, and		Northern waiting area damaged fluorescent light fixtures (2'-0" \times 2'-0"): 6 EA.	No		No		FEMA	Q3 2019	TBD	TBD
		Runway.		Damaged glass window (2'-0" x 1'-6"): 1 EA.	No		No		FEMA	Q3 2019	TBD	TBD
				Window sealant damaged: 40'-0" + 40'-0" Northeast Exit ceiling and wall drywall damaged two-sided: (17'-0" x 10'-	No		No		FEMA	Q3 2019	TBD	TBD
			Service Contract	0") x 2	No		No		FEMA	Q3 2019	TBD	TBD
			First Floor	First floor bathrooms, suspended ceiling damage: (11'-0" s 17'-0") x 2	No		No		FEMA	Q3 2019	TBD	TBD
1				First floor damaged 1'-6" diameter light fixtures: 25 EA	No		No		FEMA	Q3 2019	TBD	TBD
1				Elevator damaged: (approximately 9'-0" x 9'-0" x 5'-0")	No		No		FEMA	Q3 2019	TBD	TBD TBD
				Spiral staircase glass railing damaged: (6'-0" x 2'-0") x 7 Smoke alarm system damaged (no fire sprinklers present): (6000 SQ.	No No		No No		FEMA FEMA	Q3 2019	TBD	
				FT.) x 2 Mold remediation 1st and 2nd floor: (4784 SQ. FT. per floor) = 9568 SQ.	No		No		FEMA	Q3 2019	TBD	TBD
				FT. Information desk drywall damaged: ((11'-0" x 8'-0") x 2) + ((15'-0" x 8'-	No		No		FEMA	Q3 2019	TBD	TBD
1 /				0") x 2) + (11'-0" x 15'-0") Operations office drywall damaged: (21'-0" x 10'-0")	7.77		2.219.00		60000 (00000)	Q3 2019	TBD	TBD TBD
1				Damaged vinyl flooring: (21'-0" x 10'-0")	No No		No No		FEMA FEMA	Q3 2019 Q3 2019	TBD TBD	TBD
				Airline booths drywall damaged: ((10'-0" x 8'-6") + (10'-0" x 8'-6")) x 3	No		No		FEMA	Q3 2019	TBD	TBD
1				Fluorescent fixtures damaged: 7 (4'-0" x 2'-0")	No		No		FEMA	Q3 2019	TBD	TBD
				Second floor bathrooms, suspended ceiling damage: (11'-0" x 17'-0") x 2	No		No		FEMA	Q3 2019	TBD	TBD
				Second floor bathroom fluorescent fixtures damaged: 4 (4'-0" x 2'-0")	No		No		FEMA	Q3 2019	TBD	TBD
				Second floor drywall damaged (finish/painting required): 3(31'-6" x 16'-0") x 8	No		No		FEMA	Q3 2019	TBD	TBD


Antonio Rivera Rodriguez Airport (VQS)

Antonio Rivera Rodriguez Airport (VQS)

Site Inspection				_		Completed		On-Going		Not Started			
Date	Damage Date	Description	Area Affected	Damage	Yes/No	Date	Yes/No	Completion Date	Responsible Party	Start Date	Project Duration	Project Cost	
Storage Building													
10/20/2018	On September the 20th 2017, Hurricane Maria's wind and rain caused subsequent damages and flooding to Antonio Rivera Rodriquez Airport Main Terminal and the associated facilities. Antonio Rivera Rodriquez Airport is composed of the following: Main Terminal Building, Building #1, Air Rescue Building, Hanger #1, and Runway. Exterior Damaged rolling door: (12'-0" x 14'-0") Damaged metal flashing: (1'-0" x 12'-0") Damaged metal gutters: (40'-0') Damaged metal downspouts: (4 x 16'-0") Damaged corrugated metal siding: (16'-0" x 12'-0")		No No No No		No No No No		FEMA FEMA FEMA FEMA FEMA	TBD TBD TBD TBD TBD	TBD TBD TBD TBD TBD	TBD TBD TBD TBD TBD TBD			
			General Site										
10/20/2018	Maria's wind and damages and flo Rodriquez Airpo	On September the 20th 2017, Hurricane Maria's wind and rain caused subsequent damages and flooding to Antonio Rivera Rodriquez Airport Main Terminal and the associated facilities. Antonio Rivera	Entire Perimeter /	Damaged chain link security fencing with three strand barb wire: 2149 LIN. FT.	No		No		FEMA	TBD	TBD	TBD	
10,20,2010	9/20/2017	Rodriquez Airport is composed of the	Sito	Damaged generator: 300 Kw	No		No		FEMA	TBD	TBD	TBD	
		following: Main Terminal Building, Building	0.000000	Damaged concrete lighting poles: (30'-0") 10 EA.	No		No		FEMA	TBD	TBD	TBD	
		#1, Air Rescue Building, Hanger #1, and		Damaged exterior pole sodium lights: (400 Watt) 20 EA.	No		No		FEMA	TBD	TBD	TBD	
		Runway.		Damaged decorative light poles 10'-0": 6 EA.	No		No		FEMA	TBD	TBD	TBD	
				Damaged decorative sodium light fixtures 200 watt: 6 EA.	No		No		FEMA	TBD	TBD	TBD	
				Damage 1.5 ton condensing units: 4 EA.	No	L	Na		FEMA	TBD	TBD	TBD	

Antonio Rivera Rodriguez Airport (VQS)

APPENDIX C PMMP PAVEMENT




Source: PRPA and Kimley Horn and Associates, Inc, 2016

<u>APPENDIX D</u>

FAA FORM 5010-1 MASTER RECORD

	ENT OF TRANSP TION ADMINISTF		ORT MAST	ER RECC	RD	PRINT DATE AFD EFF FORM APPR	: 04/02/2021 03/25/2021 OVED OMB 2120-0	
> 1 ASSOC CITY: > 2 AIRPORT NAME: 3 CBD TO AIRPORT (N	ANTON	E VIEQUES NIO RIVERA RODRIGUEZ	4 STATE: PR 6 REGION/ADO:	ASO /ATL	7 SECT AE	/QS PUERTO RICO, PR RO CHT: PUERTO IN ISLANDS	FAA SITE NR:	53085.1*A
10 OWNERSHIP: > 11 OWNER: > 12 ADDRESS: > 13 PHONE NR: > 14 MANAGER: > 15 ADDRESS: > 16 PHONE NR: > 17 ATTENDANCE SCH	PUBLIC PUERTO RICO F HC-01 BOX 9421 VIEQUES, PR 0 787-729-8715 RAMON RODRIC ANTONIO RIVEF VIEQUES, PR 0 787-729-8715	I 0765-9244 GUEZ VAZQUEZ RA RODRIGUEZ AIRPORT,	HC-01 BOX 9421	> 70 FUEL: > 71 AIRFRAM > 72 PWR PLA > 73 BOTTLE (> 74 BULK OX' 75 TSNT STG 76 OTHER S	NT RPRS: NO DXYGEN: NO YGEN: NO DRAGE: TIE	NE NE NE NE	90 SINGLE ENG 91 MULTI ENG: 92 JET: 93 HELICOPTER TOTAL: 94 GLIDERS: 95 MILITARY: 96 ULTRA-LIGHT	31 2 0 2S: 0 33
MONTHS All	DAYS ALL	HOURS 0600-183	80					
18 AIRPORT USE: 19 ARPT LAT: 20 ARPT LONG: 21 ARPT ELEV: 22 ACREAGE: > 23 RIGHT TRAFFIC: > 24 NON-COMM LANDI 25 NPIAS/FED ACREE > 26 FAR 139 INDEX:	PUBLIC 18-8-5.3 65-29-3 49.0 SU 124 27 NG: YES	: 32N ESTIMATED		> 80 ARPT BCN > 81 ARPT LGT BCN LGT: 3 82 UNICOM: 5 83 WIND IND 84 SEGMENT 85 CONTROL 86 FSS: 87 FSS ON AI 88 FSS PHON 89 TOLL FRE	SKED: SKED: ICATOR: IED CIRCLE: TWR: RPT: IE NR:	IES CG SS-SR 123.000 YES-L YES NO SAN JUAN NO 1-800-WX-BRIEF	OPERA 100 AIR CARRIE 102 AIR TAXI: 103 G A LOCAL: 104 G A ITNRNT 105 MILITARY: TOTAL: OPERATIONS FORMONTHS ENDIN	R: 8,046 20,352 100 : 1,750 650 30,898
RUNWAY D. RUNWAY IDENT: 30 RUNWAY IDENT: 31 LENGTH: 32 WIDTH: 33 SURF TYPE-COND: 34 SURF TREATMENT 35 GROSS WT: 36 (IN THSDS) 37 38 39 PCN: LIGHTING/APC LIGHTING/APC 40 EDGE INTENSITY: 42 RWY MARK TYPE-C 43 VGSI: 44 THR CROSSING HC 45 VISUAL GLIDE ANG: 46 CNTRLN-TDZ: 47 RVR-RVV: 48 REIL: 49 APCH LIGHTS: OBSTRUCTION 50 FAR 77 CATEGORY 51 DISPLACED THR: 52 CTLG OBSTN: 53 OBSTN MARKED/LC; 54 HGT ABOVE RWY E 55 CIST FROM RWY E 55 CIST FROM RWY E 56 CNTRLN OFFSET: 57 OBSTN CLNC SLOF 58 CLOSE-IN OBSTN: 60 TAKE OFF RUN AV 61 TAKE OFF DIST AV 61 TAKE OFF DIST AV 62 ACLT STOP DIST AV 63 LNDG DIST AVBL (IND GND)	: : : : : : : : : : : : : : : : : : :	09/27 4,301 75 ASPH-G 20.0 40.0 //// MED NPI- G / BSC- G P4L / 46 / 3.00 / - / /- / / C / B(V) 896 / TREES / ROAD / 15 / 15 201 / 201 164L / 200L 0:1 / 0:1 Y / Y 4,301 / 4,301 4,301 / 4,301 4,301 / 4,301 3,405 / 3,405						
> 110 REMARKS: A 013 EXT 5300 A 016 OR 787-741 A 024 FEE FOR A A 052 RWY 09 AL A 057 RWY 09 AP A 058 RWY 27 15	1-0515. CCFT OVER 7500 SO 30 FT. TREES CH RATIO 0:1 FN FT. TREES, 230	TEM 86 WHEN CHANGES LBS GWT. 5, 201 FT DSTC, 240 FT. L. M DSPLCD THLD OVER 15 FT. DSTC, 145 FT. R, 192 F 0 FT. DSTC, 165 FT. L.	FT. TREES, O FT.					
11 INSPECTOR: (C)		112 LAST INSP:	04/19/2017	113 49	T INFO REQ:			



APPENDIX E AIRPORT PICTURES

Overview:







Runway:





























Taxiway:

































Terminal Building:















































Terminal Apron:



































Tenant Hangars / Aprons:



























Curbfront / Parking:













ARFF:































<u>Fuel:</u>





Miscellaneous:



































<u>APPENDIX F</u>

EQUIPMENT TRANSFER LIST

Equipment and Tool Inventory Transfer for VQS

_		Г	Г	ı	14 D	Date:	11	Damester's 115	
	Item Description	Make	Model	Serial Number	Item Book Value	Condition	Under Warranty	Remaining Life (Years)	Comments
1	CAMION RESCATE	KME		N/P 26988	value		vvarranty	(Years)	
2	QUICK DASH	FORD		N/P 99653					
	BOMBA HIDRAULICA RAM HIDRAULICO	HOLMATRO HOLMATRO	2035EPA 3322UL	203500753 332201767					
	CUTTER HIDRAULICO	HOLMATRO	3020UL	302002131					
6	SPREADER HIDRAULICO	HOLMATRO	3242UL	324202725					
	HYDRAULIC HAND PUMP	BANNER	B65118	P9904001122					
	HYDRAULIC RAM MIXY EDUCTO	BANNER POK	B65119	R9905001544					
10	Moto Sierra Disco		K1260	N/P 39573					
	MOTO SIERRA CADENA	HUSGVARNA	576XP						
	HOSE CLAMP MANGAS 2 1/2 x 25'	AKRON	D25ARN						TRES MANGAS
	BOLT CUTTER 42"		DZJAKN						DOS
	FIRE AXE PICK HEAD								DOS
	FIRE AXE FLAT HEAD HOOLIGAN TOOL								DOS
	BUCKET SHOUEL								
19	MULTICUFF BP SYSTEM	ADC	SYSTEMS						
	PROXIMITY	VERIDIAN	CVCP	38727					
	PROXIMITY PROXIMITY	VERIDIAN VERIDIAN	CVCP CVCP	38723 38722					
	PROXIMITY	VERIDIAN	CVCP	38725					
	PROXIMITY	VERIDIAN	CVCP	39732					
	PROXIMITY SCBA	VERIDIAN INTERSPIRO	CVCP	38726 36720					
-	SCBA	INTERSPIRO		36725					
-	SCBA	INTERSPIRO		36721					
-	SCBA	INTERSPIRO		36724					
-	SCBA SCBA	INTERSPIRO INTERSPIRO		36723 36726					
-	SCBA	INTERSPIRO		36719					
33	BINOCULARES	NIKON	STAY FOCUS PLUS II	33698					
	RADIO BASE	ASTRON	55-10	22787					
	RADIO MOBIL RADIO MOBIL	ICOM ICOM		30143 22781					
37	LOCKERS	PENCO		33689					TRECE
38	FUENTE AGUA	HAWS		33690					
	FIST AID KID HEART START	ZEE		36413					
40	DESFIBRILLATOR	PHILIPS		36898					
	ARCHIVO	HIRSH		29122					
_	TELEFONO	AVAYA	ONE X 9608	10WZ45657089					
43	TELEFONO	AVAYA	ONE X 9608	10WZ50251280					
44	RADIO PORTATIL/CARGADOR	ІСОМ	IC-A14	2126088					
45									
57775	RADIO PORTATIL/CARGADOR		IC-A14	2126086					
	TELEVISOR STAN PARA TELEVISOR	PANASONIC		29124 29124					
-	SILLA			36702					
-	SILLA			36703					
-	SILLA SILLA			36705 36618					
	SILLA			36624					
53	SILLA			36732					
54	NEVERA	G.E.		27275					
55	Precision foam test kit	CHEMGUARD		39411					
56	DVD PLAYER	SONY		37453					
57	DVD / CD PLAYER	MAGNAVOX		37454					
58	RADIO PORTATIL/CARGADOR	MOTOROLA	R765IS	39336					
	RADIO FORTATIL/CARGADOR	MOTOROLA	170013	39330					
	RADIO PORTATIL/CARGADOR		R765IS	39337					
	SECADORA DE ROPA	MONTEQUIN		33686					
	LAVADORA DE ROPA FOTO COPIADORA	MONTEQUIN RICHO	MP501	301376401 G987X128781					
63	FOTO COPIADORA	RICHO	MP201	W3028705235					
64	EXTINTOR WHEEL UNIT		150 LBS	34334					
	EXTINTOR WHEEL UNIT EXTINTOR WHEEL UNIT		150 LBS 150 LBS	39399 34335					
67		CORDIAC							
0/	Power Heart AED G3	SCIENCE		38026					
68	POWER HEART AED GE	CORDIAC SCIENCE		38024					
	MASCARA SCBA			34951					
70	MASCARA SCBA			34940					
	MASCARA SCBA ESCRITORIO			38400 30847					
	ARCHIVO	COLE		30847 36729					
74	PORTABLE WORK LIGHT			36728					
	PORTABLE WORK LIGHT			36727					
	PORTABLE KRONOS			37703					CECENTA V CINICO
	PILE 6% AFFF 5GL. PILE PKP 50 LBS	-							SESENTA Y CINCO DOCE
79	TRACTOR NEW HOLLAND		5610	26028					
80	TALADORA 5'	ALAMO		1620					
	TRACTOR NEW HOLLAND TRIMMER RED MAX		3401DL	4630 37007337714					DOS
83	ICE MAKER KOOL AIR		O TO I D L	31001331114					5 0 3
8/1	COMPRESSOR INGERSOLL								
	RAND			34342					
	STIHL SIERRA-CADENA 20' CAJA HERRAMIENTA	WILLIAMS		33189 39352					
87	CHIPING HAMMER	MILWAKEE		36717					
88	NEVERA 3' BLANCA			33722					
89	ESCRITORIO								4 GAVETAS / 5' ANCHO
	LOCKER AZUL								6' x 45 1/2 ANCHO
	SILLA SECRETARIAL AZUL			33710					DOC
-	ARCHIVOS (CREMA)			33719 / 17874					DOS
\Box	Locker Azul Set Sillas sala Espera								TRES SILLAS 6' x 45 1/2 ANCHO
94	ROJAS								5 SILLAS X SET
	SET SILLA MARRON								4 SILLAS X UNIDAD
33									

APPENDIX G

GENERAL AIRPORT CONTRACTED SERVICES

Cliente	Start Date	End Date	Concept	Service Type
Miguel Quiñones d/b/a PMM Business Intelligence	23-Jan-2019	30-Jun-2019	Professional Services for Air Route development	Professional
ST. James Security Services, Inc.	29-Mar-2019	30-Jun-2019	Surveillance services by security guards in different facilities of the Authority.	Professional
Deya Elevator Services, Inc.	27-Mar-2019	30-Jun-2019	Maintenance and repair services for elevators and escalators at the facilities of the Ports Authority.	Professional

Source: PRPA 2019

APPENDIX H
LIST OF ACRONYMS

List of Acronyms

AAC Asphalt Concrete Overlay on Asphalt Concrete

AC Asphalt Concrete

ACIP Airport Capital Improvement Program

APBN Airport Rotating Beacon

ARFF Aircraft Rescue and Fire-Fighting

ALP Airport Layout Plan

APC Asphalt Concrete Overlay on Portland Cement Concrete

ASDA Accelerated Stop Distance Available

AST Atlantic Standard Time

ATCT Airport Traffic Control Tower

AWOS Automated Weather Observation System

BIL Bipartisan Infrastructure Law
CFR Code of Federal Regulations
CIP Capital Improvement Program
COVID-19 Coronavirus Disease 2019
FAA Federal Aviation Administration
FAR Federal Aviation Regulation

FEO Fixed Based Operator
FCT Federal Contract Tower

FEMA Federal Emergency Management Agency

FY Fiscal Year

GA General Aviation

LDA Landing Distance Available

MITL Medium Intensity Taxiway Lights

MRO Maintenance, Repair, and Overhaul hangar

NAVAIDS Navigational Aid Systems

NPIAS National Plan of Integrated Airport Systems

PAPIs Precision Approach Path Indicators
PCC Portland Cement Concrete Pavement

PCI Pavement Condition Index

PMMP Pavement Maintenance and Management Plan

PMP Pavement Management Program
PPPA Public-Private Partnership Act

PR Puerto Rico

PRASA Puerto Rico Aqueduct and Sewer Authority
PRIDCO Puerto Rico Industrial Development Company

PRPA Puerto Rico Ports Authority
REIL Runway End Identifier Lights

RAPMMP Regional Airport Pavement Maintenance and Management Plan

RVR Runway Visual Range

SF Square Feet

TAF Traffic Area Forecast

TODA Takeoff Distance Available
TORA Takeoff Run Available

TSA Transportation Security Administration

U.S. United States

VQS Antonio Rivera Rodriguez Airport

DR.
HERMENEGILDO
ORTIZ QUINONES
AIRPORT (X63)

TECHNICAL REPORT

MAY 2023





DR HERMENEGILDO ORTIZ QUINONES AIRPORT (X63)

TECHNICAL REPORT

Version No. 3.0 May 2023 Humacao, Puerto Rico RS&H No.: 242-0047-000

Prepared by RS&H, Inc. at the direction of the Puerto Rico Public Private Partnerships Authority



TABLE OF CONTENTS

1	Intro	oduction	1
	1.1 1.2	Report Disclaimers Document Contents	
	1.3	Current Condition	
	1.4	Immediate Actions Required at the Airport	
2	Airp	oort Setting and Classification	6
	2.1	Location and Regional Setting	6
	2.2	Federal Role and Classification	
	2.3	State Role and Classification	
	2.4	Operations and Management Structure	8
3	Airfi	field Facilities	11
	3.1	Runway System	11
	3.1.	1 Declared Distances	13
	3.1.2	2 Pavement Condition	13
	3.2	Taxiway System	13
	3.3	Aprons	14
	3.4	Navigational Aids	14
4	Pass	senger Terminal Facilities	16
	4.1	General Information	
	4.2	Aircraft Parking Positions	
	4.3	Terminal Building Overview	16
5	Land	dside Facilities	19
	5.1	Regional Roadway Connectivity	19
	5.2	Airport Access Roadway System	19
	5.3	Terminal Curbfront	
	5.4	Commercial Vehicle and Rental Car Facilities	
	5.5	Public Parking Facilities	19
6	Ten	ant Facilities	20
	6.1	Cargo Facilities	
	6.2	General Aviation Facilities	
	6.3	Other Tenant Facilities	20
7	Airp	oort Support Facilities	21
	7.1	Airport Traffic Control Tower	
	7.2	Aircraft Rescue and Fire-Fighting Facilities	
	7.3	Airport Maintenance Facilities	
	7.4	Aircraft Fueling Facilities	21

7.5	Additional Airport Developable Areas	21
8 Avi	iation Activity Summary	23
8.1	Historic Aviation Activity	23
8.1	I.1 Passenger Activity	23
8.1		
8.1	1.3 Aircraft Operations	23
8.1	.4 Based Aircraft	23
8.2	Future Aviation Activity Projections	25
8.2	2.1 Passenger Activity	26
8.2		
8.2	2.3 Based Aircraft	28
9 Cap	pital Improvement Program	29
9.1	Current ACIP Summary	29
9.2	Bipartisan Infrastructure Law	
Appendi	lix A Airport Layout Plan	30
	lix B FEMA Repairs	
Appendi	lix C FAA Form 5010-1 Master Record	37
Appendi	lix D Airport Pictures	39
Appendi	lix E Equipment List Transfer	46
Appendi	lix F General Airport Contracted Services	48
Appendi	lix H List of Acronyms	50

LIST OF TABLES

Table 3-1 Runway Charcteristics	11
Table 3-2 Declared Distances	13
Table 3-3 Taxiway Characteristics	14
Table 3-4 Apron Characteristics	
Table 3-5 NAVAIDs	15
Table 6-1 Tenant Activity	20
Table 8-1 Historic – X63 Airport Statistics	24
Table 8-2 Aviation Forecasts - X63 (2022-2042)	25
Table 9-1 Airport Capital Improvement Program and Funding Sources	29
LIST OF FIGURES	
	7
Figure 2-1 Airport Location and Vicinity Map	
Figure 2-2 Airport Management Organizational Chart	
Figure 4-1 X63 Landside and Tenant Facilities	
Figure 4-2 Terminal Administrative Space	
Figure 7-1 Airport Developable Areas	
Figure 8-1 Enplaned Passengers Forecast (2022-2042)	
Figure 8-2 Operations Forecast (2022-2042)	27
Figure 8-2 Based Aircraft Forecast (2022-2042)	20

1 INTRODUCTION

The Government of Puerto Rico through the Puerto Rico Public Private Partnerships Authority (PPPA) is exploring the possible transfer of the operation, maintenance, development, and administration of nine regional airports to the private sector through a Public Private Partnership (P3). This includes the Dr Hermenegildo Ortiz Quinones Airport (X63or the Airport) in Humacao. The Public-Private Partnership Authority Act (Act 29) requires the PPPA to conduct a study on desirability and convenience to determine whether establishing such partnership is advisable.

1.1 REPORT DISCLAIMERS

The main objective of this technical report is to provide readers with a high-level technical overview of Dr Hermenegildo Ortiz Quinones Airport in support of the Desirability and Convenience Study required by Act 29. The report and its content are only provided for informational purposes and its content should not be construed as a conditions report or any other form of technical report. Even though the information included in the report was obtained from the Puerto Rico Ports Authority and other reliable sources, RS&H, Inc. does not make any warranties about their completeness, reliability, or accuracy. Use of the information included in this report is at the risk of the user/reader.

1.2 DOCUMENT CONTENTS

The main purpose of this document is to provide readers with a high-level overview of existing facilities and operational areas of the Airport.

The report is organized under the following topics:

- » Airport Setting and Classification;
- » Airfield Facilities;
- » Passenger Terminal Facilities;
- » Landside Facilities;
- » Tenant Facilities;
- » Airport Support Facilities;
- » Aviation Activity Summary;
 - Historic Aviation Activity;
 - Future Aviation Activity Projections; and
- » Capital Improvement Program.

1.3 CURRENT CONDITION

The following pictures provide a visual representation of current conditions of each of the major components at the Airport as of the middle of January 2019. Additional pictures are provided in **Appendix D** to this report.

Appendix B to this report, provides a list of repairs identified by PRPA to the Federal Emergency Management Agency (FEMA) as damages caused by Hurricane Maria in September 2017. These repairs are to be funded by FEMA. The preliminary cost estimates for X63 are approximately \$500,000 with an estimated project progression of 30 percent. FEMA repairs are projected to commence in Q1 2020.¹

General Overview





Source: RS&H, Inc. 2019

Runway





Source: RS&H, Inc. 2019

¹ The preliminary cost, project progress, and date of commencement are estimated values and the actual value and commencement of the repairs might change once the procurement process is implemented. Some of the repair projects are being implemented by PRPA and are included in the capital improvement plan included in section 9.1.

Taxiway





Source: RS&H, Inc. 2019

Terminal Apron





Source: RS&H, Inc. 2019

Terminal Building





Source: RS&H, Inc. 2019

Access Road, Curbfront and Parking





Source: RS&H, Inc. 2019

1.4 IMMEDIATE ACTIONS REQUIRED AT THE AIRPORT

On March 22, 2019, PRPA received notice from the FAA for immediate and corrective actions at X63. The letter identified safety concerns that required immediate action detailed by the FAA. Some of the deficiencies included:

- » Pavement Condition;
- » Runway Markings;
- » Runway Lights;
- » Runway Signs;
- » Fences:
- » Foreign Object Debris (FOD);
- » Hangar Damage; and
- » Vegetation Growth.

The letter highlights two grant assurances: Grant Assurance 19, *Operation and Maintenance* (Title 49 U.S.C 47107(a)(8)) and Grant Assurance 20, *Hazard Removal and Mitigation* (Title 49 U.S.C. 47107(a)(9)). PRPA must comply with these two grant assurances and provide a safe and serviceable airport, airspace, and facilities in order to be eligible for Airport Improvement Program funding and operate the Airport. X63 will remain closed until the actions identified in the letter are corrected.

On March 29, 2019, PRPA responded to the March 22, 2019, letter from the FAA requiring immediate action from the Ports Authority. X63 was closed and PRPA affirmed corrective actions are still in progress to reopen the airport. PRPA also mentioned they are currently evaluating the advantages and disadvantage of closing X63, requesting a land release, and executing an RFP for operation and maintenance of the Airport.

On April 17, 2019, PRPA responded to the March 22, 2019, letter requesting immediate action at the Airport including:

- Suspended operations at X63 with NOTAMs identifying the Airports closure until the deficiencies are corrected.
- Develop a Corrective Action Plan (CAP) and submit to the FAAA for review.

Operations were suspended on the March 29, 2019, response. To address the CAP, PRPA completed the following:

- » Windsock Replacement;
- » FOD Control;
- » Fence Repair;
- » Wildlife Control;
- » Debris Removal;
- » Runway Light Repair;
- » Runway Signs Repair;
- » Runway Markings Repair;
- » Fire Extinguisher and Certification;
- Developed Airport Operational Plans (Airport Conditions Report NOTAM, Self-inspections, Wildlife Management, Pave Areas and Safety Areas, and Markings, Signs, and Lighting and Traffic and Wind Direction Indicators).
- » Lawn Maintenance; and
- » Spare Parts Inventory.

The correspondence is provided in **Appendix G** to this report. The result is X63 will remain closed until all repairs are completed, the Airport is re-inspected, and PRPA submits the Airport for reopening. The long-term plan for X63 is to remove the property from PRPA airport system and request a land release for sale. PRPA will be in charge of the remediation action plan with the help of the operator.

2 AIRPORT SETTING AND CLASSIFICATION

2.1 LOCATION AND REGIONAL SETTING

The Municipality of Humacao is located in the central portion of the eastern coast of Puerto Rico, approximately 36 miles southeast of San Juan. Based on the 2010 U.S. Census, the population of the Municipality of Humacao was 50,896².

The Airport is located approximately 2.3 miles southeast of the Humacao city center, just east of Puerto Rico Route 53. **Figure 2-1** shows the Airport's general location and vicinity.

2.2 FEDERAL ROLE AND CLASSIFICATION

The Federal Aviation Administration (FAA) through the National Plan of Integrated Airport Systems (NPIAS) has designated X63 as a nonprimary basic general aviation service airport. General aviation airports are public-use airports with less than 2,500 annual passengers and no scheduled service. The FAA and aviation community completed further analysis on general aviation airports to capture the diverse functions and economic contribution the airport provides to the community and nation. The basic role links to the community with the national airport system and supports general aviation (GA) activities³.

2.3 STATE ROLE AND CLASSIFICATION

The PRPA Aviation System Plan defines four functional levels in their classification system for Puerto Rico's airports:

- » International Commercial;
- » Large Commercial;
- » Regional Commercial; and
- » General Aviation.

X63 was classified in a fifth category that was created in the Aviation System Plan to include airports that PRPA was considering closing due to facility redundancies or low activity. PRPA wished to examine if the facilities and services at X63 would be required in a future aviation system that includes the redeveloped Roosevelt Roads (RVR) airport. RVR was planned to possess all of the same facilities and services of X63 without capacity and developmental constraints.⁴

² https://www.census.gov/quickfacts/humacaomunicipiopuertorico

³ National Plan of Integrated Airport Systems, 2023-2027, Federal Aviation Administration

⁴ Puerto Rico Interactive Planning System Technical Report, Puerto Rico Aviation Demand Classification Definitions, Wilbur Smith Associates, 2007.

FIGURE 2-1
AIRPORT LOCATION AND VICINITY MAP



Source: RS&H, Inc., 2021

2.4 OPERATIONS AND MANAGEMENT STRUCTURE

PRPA currently uses the following structure to manage the nine Airports. At the top of the administrative structure is the Director of the Aviation Bureau, who oversees the administration for all nine Airports. Each Airport has a designated manager supervised by the Director of the Aviation Bureau. **Figure 2-2** provides a general organization chart for the aviation bureau. The Airport Manager for each Airport is responsible for directing, coordinating, and reviewing all aircraft operations, maintenance of the airfield, facilitating community relations, overseeing finances, and reporting Airport statuses to the Director. The Airport Manager is responsible for the following:

- » Airport personnel and scheduling;
- » Airport Operations;
 - X63 is fully staffed from 0730 1600⁵
- » Airport Maintenance
- Support and Coordinate with the Authority's Engineering and Construction Bureau implementation of repairs and Capital Projects;
- Development of the Airport to include evaluating needs, studying areas of improvement, and implementing plans for improvement;
- » Anticipated Capital Improvement Projects; and
- » Daily Airport Safety and Security Inspections.

Major Airport improvement and repairs at all Airports are executed through a centralized Capital Improvement Program (CIP) managed by the Authority's division of planning and engineering. The CIP helps identify a list of projects, their priority, and implementation timeline for the Airport over a five-year period. The CIP is reviewed and approved on an annual basis by the Authority's Board and eligible projects are coordinated with the FAA. The projects are then funded from various funding sources including FAA grants and Authority's own funding.

The number one responsibility of the Authority and each Airport manager is to provide for the safety and efficiency of the Airport. The Airport Manager is not only responsible for reporting to the Director, but the Airport Manager is also responsible for conveying the Airport functions and activities to the community. The management functions included in the role of Airport Manager are:

- » Planning;
- » Organizing;
- » Staffing;
- » Leading; and
- » Controlling.


PRPA manages the nine publicly owned airports and are subject to a number of Federal, State, and Local regulations. These regulations help to regulate aircraft, airmen, airports, and airspace. The Federal

⁵ https://www.airnav.com/airport/X63

Regulations are identified in *Title 14 U.S. Code of Federal Regulations (CFR), Chapters I and II, Federal Aviation Regulations (FARs) and Title 49 CFR code (DHS-TSA).*

Additional standards and guidance used by the Authority can be found in the FAA Advisory Circular 150 series. The Authority also operates the Airports under the state and local regulations pertaining to stormwater runoff, wetland protection, zoning, labor requirements, wage rates, working hours, and noise ordinances.

FIGURE 2-2 AIRPORT MANAGEMENT ORGANIZATIONAL CHART



Source: PRPA, 2019

3 AIRFIELD FACILITIES

This section summarizes existing airfield facilities at the Airport. These facilities include runways, taxiways, apron areas, and navigational aids. The existing layout of the airfield is shown in **Figure 3-1** and the airport layout plan is displayed in **Appendix A** to this report.

3.1 RUNWAY SYSTEM

The existing runway configuration at X63 consists of a single runway, designated Runway 10-28, and is a 2,458-foot long by 60-foot-wide asphalt runway oriented in an east/west direction. The runway's surface is in poor condition, and it has basic markings which are also in poor condition. The runway has a weight bearing capacity of 12,000 lbs. for single wheel aircraft.

Table 3-1 provides detailed information on the Airport's runway system and **Appendix C** to this report, contains the Airport Master Record, FAA Form 5010-1.

TABLE 3-1
RUNWAY CHARCTERISTICS

Characteristic		Runway	10-28	
Length (ft.)		2,45	8	
Width (ft.)		60		
Runway Surface Ty	/pe	Aspha	alt	
Runway Surface Co	ondition	Poo	r	
Runway Surface Tr	eatment	-		
Load Bearing	Single Wheel	12,000	lbs.	
Capacity (lbs.)	Dual Wheel	-		
	Dual Wheel Tandem	-		
	Dual Wheel Double Tandem	-		
Runway Edge Ligh	t Intensity	Medium Ir	ntensity	
Runway End		10	28	
Markings/Condition	on	Poor	Poor	
Visual Glide Slope Indicator		No	No	
Displaced Threshold		No	No	
Runway End Indica	Runway End Indicator Lights		No	
Approach Lights		No	No	

Source: FAA Form 5010-1: Airport Master Record, Accessed February 2021; PRPA, 2021

FIGURE 3-1 X63 AIRFIELD LAYOUT



Source: RS&H, Inc., 2019

3.1.1 Declared Distances

Declared distances identify different lengths of runway pavement available for various aircraft operations due to different circumstances. The declared distances at X63 equal the full extent of the runway pavement for Takeoff Run Available (TORA), Takeoff Distance Available (TODA), Accelerate Stop Distance Available (ASDA), and Landing Distance Available (LDA).

The declared distances of X63 are shown in **Table 3-2**.

TABLE 3-2
DECLARED DISTANCES

Runway	TORA (ft.)	TODA (ft.)	ASDA (ft.)	LDA (ft.)
10	2,458	2,458	2,458	2,458
28	2,458	2,458	2,458	2,458

Source: FAA Form 5010-1; Airport Master Record, Accessed February 2019; PRPA, 2019

3.1.2 Pavement Condition

X63 was not included in the 2016 PRPA Regional Airport Pavement Maintenance and Management Plan (RAPMMP). As a result, no Pavement Condition Index (PCI) information is readily available for the Airport. **Appendix D** to this report, contains photos of the current runway condition from the site visit conducted for this assessment.

PRPA is in the process of rehabilitation several pavement areas in the runway and apron of the airport.

3.2 TAXIWAY SYSTEM

There are three unnamed taxiways at X63. For the purpose of identification in this document they will be unofficially identified as Taxiway A (located on the west side of the airfield), Taxiway B (located at the center of the airfield), and Taxiway C (located on the east side of the airfield).

Taxiway A is approximately 15 feet wide and it extends north from the Runway 10 threshold for approximately 140 feet. Taxiway B is approximately 25 feet wide and extends north from Runway 10-28 for approximately 185 feet to the Airport's main apron. Taxiway C is approximately 25 feet wide and serves as a taxiway turnaround for the Runway 28 end. The entire taxiway is approximately 470 feet long.

The **Appendix D** to this report, contains photos of the current condition of Taxiway B from the site visit conducted for this assessment.

Table 3-3 provides detailed information on the Airport's taxiway system.

TABLE 3-3
TAXIWAY CHARACTERISTICS

Characteristic		Taxiway				
Characteristic	A	В	С			
Width (ft)	15	25	25			
Surface Type	Asphalt	Asphalt	Asphalt			
Pavement Condition	Fair	Fair	Fair			
Lighting	-	MITL	-			

Source: RS&H, Inc., Airport Site Visit, January 2019.

3.3 APRONS

The Airport's only apron is identified in this report as the Main Apron. It is located on the north side of Runway 10-28, and is connected to the runway by Taxiway B. It provides multiple tie-down spaces, and access to the Airport's terminal.

The **Appendix D** to this report, contains photos of the current apron condition from the site visit conducted for this assessment. **Table 3-4** provides a summary of the apron at X63, and **Figure 3-1** displays it within the rest of the Airport.

TABLE 3-4
APRON CHARACTERISTICS

Apron Type (By usage)	Pavement Condition	Total Combined Apron Area (square feet)			
Main Apron	Fair	72,250			

Source: Google Earth, 2019.

3.4 NAVIGATIONAL AIDS

Navigational Aids (NAVAIDS) are electronic, visual, and meteorological air navigation equipment that facilitate flight operations at an airport. Visual aids include airfield lighting, which enhance flight safety during instances of inclement weather and/or darkness. Electronic aids are devices used for aircraft instrument approaches. Meteorological aids provide an airport with real time weather updates for air traffic control personnel and pilots.

There are no electronic or meteorological NAVAIDs at X63. There is an airport rotating beacon, two lighted wind cones, and medium intensity runway lights (MIRL). One wind cone is located approximately 150 ft. north of the Runway 10 threshold, and the other is in between the terminal building and the temporary hangar on the Main Apron

Table 3-5 identifies the navigational aids found at the airport. **Figure 3-1** highlights the various NAVAIDS found at the Airport.

TABLE 3-5 NAVAIDS

Electronic NAVAIDs	Runway 10	Runway 28
VOR	-	-
Glideslope	-	-
Localizer	-	-
Visual NAVAIDs	Runway 10	Runway 28
Airport Rotating Beacon (APBN)	Ye	es .
Medium Intensity Runway Lights (MIRLs)	Yes	Yes
Runway End Identifier Lights (REILs)	-	-
Threshold/Runway End Lights	-	-
Precision Approach Path Indicator (PAPI)	-	-
Segmented Circle and Wind Cone	-	-
Wind Cone	Yes	Yes
Meteorological NAVAIDs	Runway 10	Runway 28
ASOS	-	-
AWOS	-	-

Source: Puerto Rico Aviation System Plan, 2007.

4 PASSENGER TERMINAL FACILITIES

4.1 GENERAL INFORMATION

The Airport's passenger terminal is located on the north side of the Airport along CII 17 Road. The facility is a single-story building with an approximate footprint of 2,250 SF. The Airport's terminal, landside, and tenant facilities are outlined in **Figure 4-1**.

4.2 AIRCRAFT PARKING POSITIONS

The terminal apron has two marked tie-down spaces for small transient aircraft. The terminal building contains a single holdroom with terminal ramp access for passengers. The remaining apron space provides unmarked parking for based aircraft that can accommodate approximately eight small aircraft.

4.3 TERMINAL BUILDING OVERVIEW

The existing terminal building provides air passenger services and recreational/tourism activity. The terminal has one counter to provide services for the general aviation traffic and a single holdroom. There is no secure area within the terminal building or security screening services.

Figure 4-2 shows the terminal layout and the administrative space currently designated for and operated by PRPA within the Airport terminal.

FIGURE 4-1 X63 LANDSIDE AND TENANT FACILITIES





Source: RS&H Inc., 2021









FIGURE 4-2 TERMINAL ADMINISTRATIVE SPACE



Source: PRPA, 2019

5 LANDSIDE FACILITIES

This section describes the airport access roadways system, including off-airport and on-airport roadways, terminal curbside areas, public and employee parking facilities, and rental car facilities.

5.1 REGIONAL ROADWAY CONNECTIVITY

Roadway access to the passenger terminal building and parking lot is available by way of CII 17 Road. From CII 17 road and traveling west, access to the regional roadway network is available via CII Marginal Oeste which ends at PR-53 Tollway approximately 0.6 miles to the north. From CII 17 road and traveling west, access to the regional roadway network is available via PR-923 which ends at PR-3 roadway approximately 0.85 miles to the northwest and PR-3 ends at PR-53 Tollway approximately 0.4 miles to the east.

5.2 AIRPORT ACCESS ROADWAY SYSTEM

Airport facilities are located on the north side of the airfield and are accessed primarily by CII 17, CII Marginal Oeste, and PR-923. CII17, CII Marginal Oeste, and PR923 are two lane two-way roadways.

5.3 TERMINAL CURBFRONT

The Airport does not have a dedicated terminal curbfront area. All vehicles are required to park in the Airport's parking lot in front of the terminal building.

5.4 COMMERCIAL VEHICLE AND RENTAL CAR FACILITIES

There are no commercial vehicle or rental car facilities on airport property.

5.5 PUBLIC PARKING FACILITIES

The Airport has one free public parking facility located adjacent to the passenger terminal. The public parking lot is approximately a 12,000 sf paved asphalt surface with lighting. The parking lot consists of approximately 50 parking stalls.

6 TENANT FACILITIES

6.1 CARGO FACILITIES

There are no cargo facilities located on the airport.

6.2 GENERAL AVIATION FACILITIES

X63 has one flight school, FAS Aviation, located on airport property. FAS Aviation provides flight training services for students.

6.3 OTHER TENANT FACILITIES

Table 6-1 provides a list of tenants at the Airport. Tenants at X63 are constantly evolving with the construction of new contracts/tenants, the renewal of existing contracts, or the expiration of terminating contracts. The list of tenants provided below is from a snapshot in time and may not accurately reflect the existing conditions.

Xtreme divers is located in the northeast portion of the airfield, directly east of the terminal apron, and provides skydiving services.

TABLE 6-1
TENANT ACTIVITY

Lessee	Term of Contract	Date Signed	Contract Expiration Date	Object of the Lease
Xtreme Divers, Inc.	5 yrs.	06-Mar-2014	06-Mar-2019	Open area (paragliding lessons, etc.)
Xtreme Divers, Inc.	Remaining Time.	30-Aug-2016	06-Mar-2019	To include clause regarding compliance with laws and regulations and FAA "Grant Assurance"
John A. Williams Bermudez	5 yrs.	11-Dec-2002	11-Dec-2007	Lot 3 (open).
Benjamin Torres Cordero D/B/A Father and Son Ultralights	2 yrs. (1-Jul-94)	13-May-1997	30-Jun-1996	Construction of Hangar.
Hydra Caribbean, Inc.	5 yrs.	15-Mar-2005	15-Mar-2010	Reconstruction of Hangar and construction of new adjacent hangar and use as aircraft storage and repair areas.
Diego Vidal Gonzalez	5 yrs.	31-Dec-2004	31-Dec-2009	Construction of Hangar and aircraft storage (Lot 1)
Benjamín Torres Cordero	5 yrs.	18-Nov-2014	30-Nov-2019	
Borinquen Lawn Service, LLC	5 yrs.	13-Oct-2016	12-Oct-2021	
Hydra Caribbean, Inc Hnc Gabriel Espasas	2 yrs.	14-Mar-2010	31-Dec-2012	
Puerto Rico Highway and Transportation Authority	99 yrs.	28-Jun-1994	27-Jun-2093	

Source: PRPA, 2019

Note: Red text identifies expired contracts

7 AIRPORT SUPPORT FACILITIES

7.1 AIRPORT TRAFFIC CONTROL TOWER

X63 does not have an Airport Traffic Control Tower (ATCT).

7.2 AIRCRAFT RESCUE AND FIRE-FIGHTING FACILITIES

X63 is not a certificated Part 139 airport and therefore does not require Aircraft Rescue and Fire-Fighting (ARFF) facilities.

7.3 AIRPORT MAINTENANCE FACILITIES

There are no airport maintenance facilities located within the Airport property.

7.4 AIRCRAFT FUELING FACILITIES

There are no dedicated fueling facilities or fuel tanks on airport property.

7.5 ADDITIONAL AIRPORT DEVELOPABLE AREAS

There are two main development opportunities on airport property at X63 as shown on **Figure 7-1**. Both areas are located on the north side of the runway on either side of the Main Apron and terminal building. The Airport's 1993 Airport Layout Plan (ALP) shows additional GA apron and hangar development and fueling facilities in these areas for future development.

FIGURE 7-1 AIRPORT DEVELOPABLE AREAS



Source: RS&H, Inc., 2021

8 AVIATION ACTIVITY SUMMARY

This section presents historic and available projections of aviation activity at the Airport. The sections presenting historic aviation activity focus on enplaned passengers (number of passengers boarding commercial service and chartered flights), aircraft operations (landings and take-offs by aircraft), and based aircraft (those aircraft permanently stored at the Airport).

The PRPA generally reports its passenger numbers and other airport related statistics for its fiscal year (FY) which runs from July 1 to June 30, as such all airport statistics included in this section of the report are shown for the Puerto Rico fiscal year.

Projections of aviation activity at the Airport into the future were not developed specifically for this report. Projections shown in this section are taken from the FAA's Terminal Area Forecast (TAF) 2022 published in March 2023.

8.1 HISTORIC AVIATION ACTIVITY

8.1.1 Passenger Activity

Historically, X63 has not had a great number of enplanements. From 2001-2006, the Airport averaged 5,000 annual enplanements, but from 2007-2019 it dropped to only 484. The worldwide COVID-19 pandemic (or Public Health Emergency) dropped enplanements to 0 in 2020, but has since surpassed prepandemic levels with 2,365 enplanements in 2022.

The second column in **Table 8-1** show the enplanements from 2001 to 2022.

8.1.2 Air Service

There is no scheduled commercial air service currently at the Airport. None is anticipated in the near future.

8.1.3 Aircraft Operations

An aircraft operation is defined as either a takeoff or a landing. Airfield activity at an airport is measured and forecast according to annual aircraft operations. Historically, the airport has been a general aviation airport. Over the past 20 years, the Airport saw its greatest number of operations between 2001-2011 with over 5,000 operations annually. Operations dropped to 2,527 between 2012-2018 and then to 0 during the COVID-19 pandemic, but has since increased with 3,674 operations in 2022.

The third column in **Table 8-1** shows the operations from 2001 to 2022.

8.1.4 Based Aircraft

As an airport primarily used for general aviation customers, X63 has averaged 25 based aircraft over the past 20 years. In 2011, it dropped to four and then again to three in 2015. However, it was able to sustain 9 based aircraft amidst the Public Health Emergency.

The fourth column in **Table 8-1** shows the operations from 2001 to 2022.

TABLE 8-1 HISTORIC – X63 AIRPORT STATISTICS

Fiscal Year	Enplanements	Operations	Based Aircraft
2001	4,576	5,349	35
2002	7,351	5,349	35
2003	5,254	5,349	35
2004	6,267	5,349	35
2005	4,824	5,349	35
2006	2,136	5,349	35
2007	627	5,349	35
2008	607	5,349	35
2009	785	5,349	35
2010	907	5,349	12
2011	492	5,349	4
2012	766	2,527	23
2013	927	2,527	27
2014	636	2,527	27
2015	2,175	2,527	3
2016	2,135	2,527	22
2017	615	2,527	20
2018	386	2,527	20
2019	484	725	20
2020	0	0	9
2021	1,707	2,174	9
2022	2,365	3,674	9

Source: PRPA Records: FAA TAF 2022; FAA 5010 Form, 2022

8.2 FUTURE AVIATION ACTIVITY PROJECTIONS

This section provides the FAA derived forecast identified as the FAA TAF 2022. The FAA TAF is an annual forecast prepared by the FAA and includes projections of operations by type, based aircraft counts, and projections of enplanements. The FAA TAF 2022 published by the FAA in March 2023, was used for the forecast of aviation activity from 2022-2042⁶.

Table 8-2 shows the aviation forecasts for X63 from 2022-2042.

TABLE 8-2

AVIATION FORECASTS - X63 (2022-2042)

Fiscal Year	Enplanements	Operations	Based Aircraft		
2022	2,365	3,674	9		
Forecast					
2023	2,365	3,674	9		
2024	2,365	3,674	9		
2025	2,365	3,674	9		
2026	2,365	3,674	9		
2027	2,365	3,674	9		
2028	2,365	3,674	9		
2029	2,365	3,674	9		
2030	2,365	3,674	9		
2031	2,365	3,674	9		
2032	2,365	3,674	9		
2033	2,365	3,674	9		
2034	2,365	3,674	9		
2035	2,365	3,674	9		
2036	2,365	3,674	9		
2037	2,365	3,674	9		
2038	2,365	3,674	9		
2039	2,365	3,674	9		
2040	2,365	3,674	9		
2041	2,365	3,674	9		
2042	2,365	3,674	9		
	Annual	Growth Rate			
2022-2032	0.0%	0.0%	0.0%		
2032-2042	0.0%	0.0%	0.0%		
2022-2042	0.0%	0.0%	0.0%		

Source: FAA TAF 2022; RS&H 2023

-


⁶ While the growth rate for the 2022-2042 projections was used for annual enplanements, operations, and based aircraft, the 2022 totals varied in some instances where PRPA records showed differences. As a result, these totals were sometimes carried forward in forecasts that had no growth shown in the FAA TAF 2022, but still may be referenced as the FAA TAF 2022 Forecast.

8.2.1 Passenger Activity

The FAA TAF 2022 shows no projections for enplanements, thus the 2,365 passenger enplanements from PRPA records are projected to remain constant at 2,365 over the next 20 years.

Error! Reference source not found. displays the passenger enplanement forecast from 2022-2042.

FIGURE 8-1 ENPLANED PASSENGERS FORECAST (2022-2042)




Sources: FAA TAF 2022; PRPA Records

8.2.2 Aircraft Operations

As the Airport works out of the impacts to the pandemic, the FAA TAF projects no growth for the 3,674 annual operations at X63 over the next 20 years.

Figure 8-2 displays the total operations forecast from 2022-2042.

FIGURE 8-2
OPERATIONS FORECAST (2022-2042)




Sources: FAA TAF 2022; PRPA Records

8.2.3 Based Aircraft

The FAA TAF 2022 shows no projections for the 9 based aircraft forecast for 2022 to increase over the next 20 years.

Error! Reference source not found. displays the based aircraft forecast from 2022-2042.

FIGURE 8-3 BASED AIRCRAFT FORECAST (2022-2042)



Sources: FAA TAF 2022; PRPA Records

9 CAPITAL IMPROVEMENT PROGRAM

This section presents the current Airport Capital Improvement Program (ACIP) for the Airport identifying capital projects that will be undertaken through 2027. Projects listed in the ACIP for X63 were provided by the PRPA⁷.

9.1 CURRENT ACIP SUMMARY

Table 9-1 presents a summary of the current 5-year ACIP for the Airport, including the estimated cost and eligible funding sources.

TABLE 9-1
AIRPORT CAPITAL IMPROVEMENT PROGRAM AND FUNDING SOURCES

Project Description	Cost	Federal Funds	PRPA	Start FY	End FY
Airfield Pavement Improvements (including safety area)	\$1,750	\$1,350	\$400	2023	2023
Construction	\$1,750	\$1,350	\$400	2023	2023
Hurricane Maria Damages Repairs	\$3,000	\$3,000	\$0	2023	2023
Subtot	al \$4,750	\$4,350	\$400		

Source: Puerto Rico Ports Authority, 2023

Notes: All costs shown in thousands of U.S. Dollars

Total 5-year ACIP project costs are estimated to be \$4.75 million through the 2027 time period. A total of 92 percent of the funding is anticipated through FAA grants with the remaining 8 percent from PRPA funds.


9.2 BIPARTISAN INFRASTRUCTURE LAW

The Bipartisan Infrastructure Law (BIL) provides \$15 billion for airport-related projects as defined under the existing Airport Improvement Grant and Passenger Facility Charge criteria. The money can be invested in runways, taxiways, safety, and sustainability projects, as well as terminal, airport-transit connections and roadway projects.

For FAA fiscal year 2023 Dr Hermenegildo Ortiz Quinones Airport will receive \$113,000. It is expected that X63 will receive a similar amount from the BIL for the next three years.

⁷ X63 CIP provided in May 2023.

APPENDIX A AIRPORT LAYOUT PLAN



Source: PRPA, 1993

APPENDIX B
FEMA REPAIRS

Humacao Regional Airport (HUC)											
_				Comple	Completed On-Going Not Started						
Space	Observations	Immediate Actions	Permanent Solutions	Yes/No	Date	Yes/No	Completion Date	Responsible Party	Start Date	Project Duration	Project Cost
	STRUCTURAL-ARCHITECTURAL							Durunon			
	There was rainwater infiltration and damaged sections of the acoustical ceiling tiles and lighting fixtures.	Remove damaged acoustical tiles.	Replace acoustical ceiling tiles and lighting fixtures.	No		No		FEMA	Q1 2020	TBD	TBD
	Missing/damaged exterior entrance metal door and frame.	Provide temporary wood paneling and seal all openings.	Replace main entrance door.	No		No		FEMA	Q1 2020	TBD	TBD
	Broken/damage interior gypsum board partitions.	No immediate action required.	Replace gypsum board walls.	No		No		FEMA	Q1 2020	TBD	TBD
Main Terminal Building	Broken/damage aluminum windows.	Provide temporary wood paneling and seal all openings.	Replace windows.	No		No		FEMA	Q1 2020	TBD	TBD
	Missing sections of roof metal decking.	Provide temporary roof covering to affected areas.	Replace affected sections of roof metal decking.	No		No		FEMA	Q1 2020	TBD	TBD
	Damaged metal deck roofing insulation.	No immediate action required.	Replace roofing insulation.	No		No		FEMA	Q1 2020	TBD	TBD
	No structural damages to report.	N/A	N/A	No		No		FEMA	Q1 2020	TBD	TBD
	Damaged structural wood frame.	Provide temporary structural support.	Replace affected structural wood frame.	No		No		FEMA	Q1 2020	TBD	TBD
Domingo Emanuelli Hangar (Rental)	Missing sections of roof metal decking.	Provide temporary roof covering to affected areas.	Replace affected sections of roof metal decking.	No		No		FEMA	Q1 2020	TBD	TBD
		Provide temporary wood paneling and seal all openings.	Replace affected sections of vertical metal siding.	No		No		FEMA	Q1 2020	TBD	TBD
Benjamin Torres Hangar (Rental)	Heavy architectural and structural damages; completely destroyed hangar	No immediate action required.	Replace aviation hangar assembly.	No		No		FEMA	Q1 2020	TBD	TBD
Charles Williams Hangar	No structural damages to report.	N/A	N/A	No		No		FEMA	Q1 2020	TBD	TBD
(Rental)		Provide temporary roof covering to affected areas.	Replace affected sections of roof metal decking.	No		No		FEMA	Q1 2020	TBD	TBD
Site	Damaged and missing sections of perimeter runway cyclone fence.	Provide temporary enclosure fence.	Replace cyclone fence.	No		No		FEMA	Q1 2020	TBD	TBD


Space Characteristics Char	Humacao Regional Airport (HUC)											
Closervations immediate Actions Permanent Solutions Very/No Date Yes/No Completion Date Responsible Party Stant Date Durestion SECTIONCAL Replace all diffusions and righting finatures and righting system. Some as immediate action No No FEMA 02 2020 TED The Approach lighting system was damaged. Applied three section of the system was damaged. Applied three section of the system and the system and the system in coord						eted	О	n-Going		Not Star		
Runway Main Terminal Building Main Terminal Building Main Terminal Building Task all branch circuits Inglying futures in effective arises or inglying futures in effective arises or inglying accommendate action Task all branch circuits Inglying & commendate action No No No FEMA C1 2020 T30 T30 T40 T50 T50 T60 T60 T60 T60 T60 T6	Space	Observations	Immediate Actions	Permanent Solutions	Yes/No	Date	Yes/No	Completion Date	Responsible Party	Start Date		Project Cost
Main Terminal Building There was rain infiltration that damaged the lighting forcers infiltration that damaged. Unition raido system was damaged. Replace UNICOM system. Same as immediate action No No No FEMA Q1 2020 TBD Wind sock was damaged. Replace wind sock. Same as immediate action No No No FEMA Q2 2020 TBD Rainway lights were damage. Applace damage. Same as immediate action No No FEMA Q2 2020 TBD Maintenance & Storage Approach lighting system was damaged. Applace approach lighting system was damaged. No No FEMA Q1 2020 TBD The was rain initiation that damage to report. Applace approach lighting system was damaged. No No FEMA Q1 2020 TBD The area was completely destroyed. No No FEMA Q1 2020 TBD The area was completely destroyed. No No FEMA Q1 2020 TBD The area was completely destroyed. No No FEMA Q1 2020 TBD			miniculate Actions								Duration	
Main Terminal Building There was rain infiltration that damaged the lighting forcers infiltration that damaged. Unition raido system was damaged. Replace UNICOM system. Same as immediate action No No No FEMA Q1 2020 TBD Wind sock was damaged. Replace wind sock. Same as immediate action No No No FEMA Q2 2020 TBD Rainway lights were damage. Applace damage. Same as immediate action No No FEMA Q2 2020 TBD Maintenance & Storage Approach lighting system was damaged. Applace approach lighting system was damaged. No No FEMA Q1 2020 TBD The was rain initiation that damage to report. Applace approach lighting system was damaged. No No FEMA Q1 2020 TBD The area was completely destroyed. No No FEMA Q1 2020 TBD The area was completely destroyed. No No FEMA Q1 2020 TBD The area was completely destroyed. No No FEMA Q1 2020 TBD			Davids and difference and									
Main Terminal Building There was rain infiltration that damaged the lighting & convenience receptacles), once energy further damage. Unicom radio system was damaged. Replace UNICOM system. Runway Runway				Same as immediate action	No		No		FEMA	Q1 2020	TBD	TBD
Main Terminal Bullding There was rain infiltration that dismaged to lighting fotures in different areas of the building. Unicom radio system was damaged. Runway Runway Runway Runway Runway Runway lights were damage. Approach lighting system was damaged. No immediate action No No No FEMA Q1 2020 TBD Maintenance & Storage Container (Rontal) Estreme Divers container (Rontal) Estreme Divers container (Rontal) There was rain infiltration that damaged the lighting futures in different areas of the building. An interval and the future in this damage of report in the part of the new han												
Main Terminal Building There was rain infiltration that dismaged the lighting fixtures in different areas of the building. Unicom radio system was diamaged. Unicom radio system was diamaged. Replace UNICOM system. Same as immediate action No No No FEMA 01 2020 TBD Wind sock was damaged. Replace UNICOM system. Same as immediate action No No No FEMA 01 2020 TBD Runway lights were damage. Runway lights were damage. Runway lights were damage. Runway lights were damage. Maintenance & Storage Container (fiental) Estreme Divers container (fiental) There was rain infiltration that damaged the lighting system was rain infiltration that damaged the lighting fixture in different areas of the building. No Infinished the system of the lighting system was rain infiltration that damaged the lighting fixture in different areas of the building. Dominge Emanuelli Hangar (fiental) The area was completely destroyed No MA Same as immediate action No Infinisholution required No Infinisholution required No Infinisholution required No Infinisholution required the lighting system was rain infiltration that damaged the lighting fixture in different areas of the building. There was rain infiltration that damaged the lighting fixture in different areas of the building. No Infinisholution required section Replace all diffusers and lighting fixtures in different areas of the building. No Infinisholution required section No No FEMA Q1 2020 TBD Tab design of the new hangar.												
There was rain infiltration that damaged the lighting fixtures in different areas of the building. Unicom radio system was damaged. Replace UNICOM system. Replace wind sock. Replace wind sock. Replace wind sock. Replace wind sock. Replace dingd. runway lights on test remaining nurway lights on every large. Runway lights were damage. Runway lights on test remaining nurway lights, one energy a restored to assess any stem. Runway lights were damage. Runway lights we	Main Terminal Building				No		No		FEMA	O1 2020	TBD	TBD
the lighting fixtures in different areas of the building. Unicon radio system was damaged. Wind sock was damaged. Replace UNICOM system. Replace UNICOM system. Same as immediate action No No FEMA 01 2020 TBD Wind sock was damaged. Replace dingd. runway lights and text remaining runway lights and text remaining runway lights once energy is restored to assess. Same as immediate action Replace dingd. runway lights were damage. Runway lights were damage. Runway lights were damage. Runway lights were damage. Approach lighting system was damaged system. Replace dingd. runway lights seried to assess any data text emailing runway lights once energy is restored to assess any data text emailing runway lights were damage. Runway lights were damage. Runway lights were damage. Replace dingd. runway lights seried to assess any data text emailing runway lights once energy is restored to assess any data text emailing runway lights once energy is restored to assess any data text emailing runway lights were damage. Runway lights were damage. Replace dingd. runway lights were damage. Replace and runway lights seried to assess any data text emailing runway lights once energy is restored to assess any data text emailing runway lights seried to assess any data text emailing runway lights seried to assess any data text emailing runway lights seried to assess any data text emailing runway lights seried to assess any data text emailing runway lights seried to assess any data text emailing runway lights seried to assess any data text emailing runway lights seried to assess any data text emailing runway lights and text emailing runway lights and light fixed	•	There was rain infiltration that damaged			200.70		10.5				1.5.5	1.5.5
Unicom radio system was damaged. Replace UNICOM system. Same as immediate action No No No FEMA Q1 2020 TBD Replace wind sock. Same as immediate action No No No FEMA Q1 2020 TBD Replace dingd. runway lights once energy is restored to assess any further damage. Approach lighting system was damaged approach lighting system was damaged system. Maintenance & Storage Container (Rental) Molectrical damage to report required No Infinal solution required No Infinal Replace Aproach Infination that damaged the lighting fixtures in different areas of the building. The area was completely destroyed NA designer of the new hangar.			is restored to assess any									
Unicom radio system was damaged. Replace UNICOM system. Same as immediate action No No No FEMA Q1 2020 TBD		the building.	further damage.	Same as immediate action								
Unicom radio system was damaged. Replace UNICOM system. Same as immediate action No No No FEMA Q1 2020 TBD					No		No		FEMA	Q1 2020	TBD	TBD
Runway Runway Runway lights were damage. Replace dingd. runway lights, once energy lights and test remaining runway lights, once energy lis restored to assess any further damage. Replace approach lighting system was damaged Approach lighting system was damaged Approach lighting system was damaged Container (Rental) Extreme Divers Container (Rental) Replace approach lighting system was damaged No lectrical damage to report No limitediate action No final solution required No final solution required No final solution required No final solution required No location required No location required No location required No No No FEMA Q1 2020 TBD Extreme Divers Container (Rental) There was rain infiltration that damaged the lighting fixtures in different areas of lighting fixtures and		Unicom radio system was damaged.	Replace UNICOM system.	Same as immediate action								
Runway lights were damage. Replace dingd. runway lights were damage. Runway lights were damage. Runway lights were damage. Runway lights were damage. Replace approach lighting system was damaged Replace approach lighting system. Same as immediate action No No No FEMA Q1 2020 TBD Replace approach lighting system was damaged Replace approach lighting system. Same as immediate action No immediate action No linal solution required No final solution required No No No FEMA Q1 2020 TBD Replace approach lighting system was damaged by system. No immediate action No linal solution required No final solution required No No No FEMA Q1 2020 TBD Replace approach lighting system was damaged by system. No immediate action No linal solution required No No No FEMA Q1 2020 TBD Replace all diffusers and lighting fixtures in different areas of the lighting fixtures in different areas of lighting fixtures are fleeted. Some as immediate action No No No FEMA Q1 2020 TBD The area was completely destroyed NA Coordinate a new electrical system in coordination with the designer of the new hangar. No No No FEMA Q1 2020 TBD					No		No		EENAA	01 2020	TRD	TBD
Runway Runway lights were damage. Runway lights were damage. Runway lights were damage. Runway lights were damage. Replace approach lighting system was damaged Approach lighting system was damaged Container (Rental) Extreme Divers Container (Rental) No electrical damage to report (Rental) No electrical damage to report No final solution required No No No No No FEMA Q1 2020 TBD There was rain infiltration that damaged the lighting fixtures in different areas of the building. Domingo Emanuelli Hangar (Rental) The area was completely destroyed NA Coordinate a new electrical system in coordination with the designer of the new hangar. No No No No FEMA Q1 2020 TBD TBD TBD TBD TBD TBD TBD TB		Wind sock was damaged.	Replace wind sock.	Same as immediate action	NO		NO		PLIVIA	Q1 2020	100	160
Runway Runway lights were damage. Runway lights were damage. Runway lights were damage. Runway lights were damage. Replace approach lighting system was damaged Approach lighting system was damaged Container (Rental) Extreme Divers Container (Rental) No electrical damage to report (Rental) No electrical damage to report No final solution required No No No No No FEMA Q1 2020 TBD There was rain infiltration that damaged the lighting fixtures in different areas of the building. Domingo Emanuelli Hangar (Rental) The area was completely destroyed NA Coordinate a new electrical system in coordination with the designer of the new hangar. No No No No FEMA Q1 2020 TBD TBD TBD TBD TBD TBD TBD TB												
Rumway lights were damage. Rumway lights were damage. Rumway lights were damage. Replace approach lighting system was damaged system. Same as immediate action No No No FEMA Q1 2020 TBD Maintenance & Storage Container (Rental) No electrical damage to report Replace approach lighting system was damaged system. No immediate action No final solution required No final solution required No final solution required No final solution required No No No FEMA Q1 2020 TBD There was rain infiltration that damaged the lighting fixtures in different areas of the building. Domingo Emanuelli Hangar (Rental) The area was completely destroyed No Mo FEMA Q1 2020 TBD Coordinate a new electrical system in coordination with the designer of the new hangar. No No No FEMA Q1 2020 TBD			Replace dmgd. runway									
Runway lights were damage. Replace approach lighting system was damaged system. Same as immediate action No No No No FEMA Q1 2020 TBD No immediate action required No final solution required No limediate action required No final solution required No limediate action required No final solution required No limediate action required No final solution required No final solution required No final solution required No final solution required No No No FEMA Q1 2020 TBD No No No FEMA Q1 2020 TBD There was rain infiltration that damaged the lighting fixtures in different areas of the building. Domingo Emanuelli Hangar (Rental) The area was completely destroyed No No No FEMA Q1 2020 TBD TBD	Runway				No		No		FEMA	Q1 2020	TBD	TBD
Runway lights were damage. further damage. Same as immediate action Replace approach lighting system was damaged. Maintenance & Storage Container (Rental) Mo electrical damage to report Replace approach lighting system was damaged. No immediate action No immediate action No final solution required No No No No No No No No FEMA Q1 2020 TBD There was rain infiltration that damaged the lighting fixtures in different areas of the building. Domingo Emanuelli Hangar (Rental) The area was completely destroyed No No No No No No No FEMA Q1 2020 TBD TBD TBD TBD TBD TBD TBD TB												
Approach lighting system was damaged Same as immediate action required No final solution required No local container (Rental) No local container (Rental) No local container (Rental) There was rain infiltration that damaged the lighting fixtures in different areas of the building. Domingo Emanuelli Hangar (Rental) The area was completely destroyed No local container (Rental) Replace all diffusers and lighting fixtures affected. Same as immediate action No local container (Rental) No local container (Rental) No local container (Rental) No local container (Rental) Replace all diffusers and lighting fixtures affected. Same as immediate action No local container (Rental) No local container (Rental) No local container (Rental) No local container (Rental) Replace all diffusers and lighting fixtures affected. Same as immediate action No local container (Rental) No local container (Rental) No local container (Rental) Replace all diffusers and lighting fixtures affected. No local container (Rental) No local container (Rental) Replace all diffusers and lighting fixtures affected. No local container (Rental) Replace area (Rental) No local container (Rental) No local conta		Runway lights were damage		Same as immediate action								
Approach lighting system was damaged system. Same as immediate action Maintenance & Storage Container (Rental) No electrical damage to report Externe Divers Container (Rental) No electrical damage to report No immediate action required No final solution required No final solution required No final solution required No final solution required No No No No No No No No No No		Ruiway ngika were damage.	NO. NO. NO. NO. NO.	Sum as immediate action								
Maintenance & Storage Container (Rental) Extreme Divers Container (Rental) No electrical damage to report No immediate action required No final solution required No No No No No No No No No No		Approach lighting system was damaged	1000	Sama as immediate action	No		No		FEMA	Q1 2020	TBD	TBD
Container (Rental) No electrical damage to report FEMA G1 2020 TBD No immediate action required No final solution required No No No No No No No No No FEMA G1 2020 TBD TBD There was rain infiltration that damaged the lighting fixtures in different areas of the building. Domingo Emanuelli Hangar (Rental) The area was completely destroyed No No No No No No FEMA G1 2020 TBD No No No FEMA G1 2020 TBD No No No FEMA G1 2020 TBD TBD		Approach lighting system was damaged		Same as inimediate action								
Extreme Divers Container (Rental) No electrical damage to report There was rain infiltration that damaged the lighting fixtures in different areas of the building. Domingo Emanuelli Hangar (Rental) The area was completely destroyed No immediate action No		No electrical damage to report		No final solution required	No		No		FEMA	Q1 2020	TBD	TBD
Rental No electrical damage to report required No final solution r		5			No		No		FENAA	01 2020	TDD	TDD
the lighting fixtures in different areas of the building. Domingo Emanuelli Hangar (Rental) The area was completely destroyed N/A Coordinate a new electrical system in coordination with the designer of the new hangar. No	(Rental)	No electrical damage to report	required	No final solution required	NO		NO		FEIVIA	Q1 2020	TBD	TBD
the lighting fixtures in different areas of the building. Domingo Emanuelli Hangar (Rental) The area was completely destroyed N/A Coordinate a new electrical system in coordination with the designer of the new hangar. No		There was rain infiltration that damaged										
the building. lighting fixtures affected. Same as immediate action Domingo Emanuelli Hangar (Rental) The area was completely destroyed N/A Coordinate a new electrical system in coordination with the designer of the new hangar. No No No FEMA Q1 2020 TBD TBD	Esparsa Hangar (Rental)		Replace all diffusers and		No		No		FEMA	Q1 2020	TBD	TBD
(Rental) The area was completely destroyed N/A designer of the new hangar. No No No FEMA Q1 2020 TBD				Same as immediate action								
The area was completely destroyed N/A designer of the new hangar. No No FEMA Q1 2020 TBD	Domingo Emanuelli Hangar			Coordinate a new electrical system in coordination with the	No		No		EENAA	01 2020	TRD	TBD
	(Rental)	The area was completely destroyed	N/A	designer of the new hangar.	NO		NO		TEIVIA	Q1 2020	100	100
					No		No		FFMA	01 2020	TBD	TBD
Thebiace an unitasets and			Replace all diffusers and									
lighting fixtures affected.			lighting fixtures affected.	1								ļ
Benjamin Torres Hangar	- 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1											
(Rental) Test all branch circuits	(Rental)		SACTOR SECURE AND SECURITION OF THE SECURITION O									
(lighting & convenience No No FEMA Q1 2020 TBD					No		No		EFMA	01 2020	TRD	TBD
leceptacies), once		There was rain infiltration that days			110		140		LIVIA	Q1 2020	טטו	160
There was rain infiltration that damaged the lectrical energy is the lighting fixtures in different areas of t												
the building. further damage. Same as immediate action				Same as immediate action								

	Humacao Regional Airport (HUC)											
				Completed		On-Going		Not Started				
Space	Observations	Immediate Actions	Permanent Solutions	Yes/No	Date	Yes/No	Completion Date	Responsible Party	Start Date	Project Duration	Project Cost	
		Replace all diffusers and lighting fixtures affected.		No		No		FEMA	Q1 2020	TBD	TBD	
Charles Williams Hangar (Rental)	There was rain infiltration that damaged the lighting fixtures in different areas of	Test all branch circuits (lighting & convenience receptacles), once energy is restored to assess any further damage.	Same as immediate action	No		No		FEMA	Q1 2020	TBD	TBD	
	There is no electrical energy from the utility available.			No		No		FEMA	Q1 2020	TBD	TBD	
	the street impeding vehicular traffic to the	Coordinate removal of poles with the electrical utility company.	Same as immediate action	No		No		FEMA	Q1 2020	TBD	TBD	
Site	Electrical service pole was damaged and the transformer serving the airport is	Coordinate the replacement of the pole and transformer with the electrical utility company.	Same as immediate action	No		No		FEMA	Q1 2020	TBD	TBD	
	Electrical energy generator not operating.	The generator needs to be replaced.	Same as immediate action	No		No		FEMA	Q1 2020	TBD	TBD	

	Humacao Regional Airport (HUC)											
				Completed On-Going				Not Star	ted			
Space	Observations	Immediate Actions	Permanent Solutions	Yes/No	Date	Yes/No	Completion Date	Responsible Party	Start Date	Project Duration	Project Cost	
			MECHANICAL									
	Condensing unit was displaced/tipped.	Reposition unit to original position and confirm its functionality.	Provide new unit if required.	No		No		FEMA	Q1 2020	TBD	TBD	
Main Terminal Building	Facility counts with potable water cistern and pumping station but lacks electric power (PREPA nor Emergency). However the building has running potable water.	No immediate action required	No final solution required	No		No		FEMA	Q1 2020	TBD	TBD	
Runway	No mechanical damage to report	No immediate action required	No final solution required	No		No		FEMA	Q1 2020	TBD	TBD	
Maintenance & Storage Container (Rental)	No mechanical damage to report	No immediate action required	No final solution required	No		No		FEMA	Q1 2020	TBD	TBD	
Extreme Divers Container (Rental)	No mechanical damage to report	No immediate action required	No final solution required	No		No		FEMA	Q1 2020	TBD	TBD	
Esparsa Hangar (Rental)	Roof gutters are broken	No immediate action required	Repair gutter	No		No		FEMA	Q1 2020	TBD	TBD	
Domingo Emanuelli Hangar (Rental)	No mechanical damage to report	No immediate action required	No final solution required	No		No		FEMA	Q1 2020	TBD	TBD	
Benjamin Torres Hangar (Rental)	No mechanical damage to report	No immediate action required	No final solution required	No		No		FEMA	Q1 2020	TBD	TBD	
Charles Williams Hangar (Rental)	No mechanical damage to report	No immediate action required	No final solution required	No		No		FEMA	Q1 2020	TBD	TBD	
Site	No mechanical damage to report	No immediate action required	No final solution required	No		No		FEMA	Q1 2020	TBD	TBD	

<u>APPENDIX C</u>

FAA FORM 5010-1 MASTER RECORD



AIRPORT PICTURES

Overview:



Runway:













Taxiway:





















Terminal Apron:

















Tenant Hangars / Apron:



Terminal Building:























Curbfront / Parking:





Miscellaneous:













<u>APPENDIX E</u>

EQUIPMENT LIST TRANSFER

Equipment and Tool Inventory Transfer for X63

Date :

	Item Description	Make	Model	Serial Number	Item Book Value	Condition	Under Warranty	Remaining Life (Years)	Comments
1	TRIMMER	STIHL							
2	TRIMMER	red Max	GZ-30N	39458					
3	BOOSTER		SOLAR ES 2,500	32382					CARGADOR DE BATERIA
1	MAQUINA LAVADO A PRESION	SUBARU 6.0		38059					
5	TALADRO	CRAFTSMAN		32380					
6	CAJA HERRAMIENTA	CRAFTSMAN		32380					
7	Maquina pulir piso			26749					DOS (2)
8	GATO HIDRAULICO			27327					. ,
9									DELTA SHOP MASTER
10	Maquina esmeril	DELTA		31080					BENCH GRANDER
11	ESCALERA 6'			37594					N/P 16047, 16046, 16045,
12	LOKERS 6			VER COMMENTS					16050, 16049, 16048
13	RADIO BASE FAA			37594					
1/	Archivos de seis gavetas	ARTOPEX		32813 / 24964					DOS (2)
15	ESCRITORIO								Madera Tipol
16	SILLA OFICINA								CUATRO (4)
	Consola A/C	TGM							A/C MINI SPLIT UNIT
	FUENTE DE AGUA	MAJOR SAFE		37602					
18	Caja fuerte (Bobeda)	COMP		5094					CAJA FUERTE TIPO BOBEDA
19	ESCRITORIO			29899					PEQUEÑO DE METAL Y MADERA
20	ESCRITORIO								Madera Secretarial
21	SILLA SECRETARIAL	KNOLL,INC	EJECUTIVA	32847					IMADEINA SECRETARIAE
22	SILLAS DE OFICINA	RIVOLL, IIVC	BECOTIVA	32041					DOS (2)
23	ARCHIVO DE 4'	CITY STATION		34786					CUATRO GAVETAS
24	ARCHIVO GRANDE 6'	CITI STATION		34700					CINCO GAVETAS
25	SET DE CUATRO SILLAS								SIETE (7) SETS
26	SET DE COATRO SILLAS								SIETE (1) SETS
27									
28									
29									
30									
31									
32									
33									
34									
35									
36									
37									
38									
39									
40									

<u>APPENDIX F</u>

GENERAL AIRPORT CONTRACTED SERVICES

Contract Services at the Airport										
Client	Start Date	End Date	Concept	Service Type						
Borinquen Lawn Services, LLC	13-Oct-2016	12-Oct-2021	Rental contract for the maintenance of green areas at the Airport	Rental						
ST. James Security Services, Inc.	29-Mar-2019	30-Jun-2019	Surveillance services by security guards in different facilities of the Authority.	Professional						

APPENDIX H
LIST OF ACRONYMS

List of Acronyms

AC Asphalt Concrete

ACIP Airport Capital Improvement Program

APBN Airport Rotating Beacon

ARFF Aircraft Rescue and Fire-Fighting

ALP Airport Layout Plan

ASDA Accelerated Stop Distance Available

AST Atlantic Standard Time

ATCT Airport Traffic Control Tower

AWOS Automated Weather Observation System

BIL Bipartisan Infrastructure Law
CFR Code of Federal Regulations
CIP Capital Improvement Program
COVID-19 Coronavirus Disease 2019
FAA Federal Aviation Administration
FAR Federal Aviation Regulation

FEMA Federal Emergency Management Agency

FY Fiscal Year

GA General Aviation

LDA Landing Distance Available

MITL Medium Intensity Taxiway Lights

NAVAIDS Navigational Aid Systems

NPIAS National Plan of Integrated Airport Systems

PAPIs Precision Approach Path Indicators

PCI Pavement Condition Index

PMMP Pavement Maintenance and Management Plan

PMP Pavement Management Program
PPPA Public-Private Partnership Act

PR Puerto Rico

PRASA Puerto Rico Aqueduct and Sewer Authority
PRIDCO Puerto Rico Industrial Development Company

PRPA Puerto Rico Ports Authority
REIL Runway End Identifier Lights

RAPMMP Regional Airport Pavement Maintenance and Management Plan

RVR Runway Visual Range

SF Square Feet

TAF Traffic Area Forecast

TODA Takeoff Distance Available

TORA Takeoff Run Available

TSA Transportation Security Administration

U.S. United States

X63 Dr. Hermenegildo Ortiz Quiñonez Airport